



ASHDOWNE HANDCRAFTED

Now with subtle, distressed edges.

Each tile is uniquely beautiful but with all the benefits of machine-made clay tiles.



THE BEAUTY OF ASHDOWNE... WITH ADDED EDGE

Advances in processing technology now give Ashdowne tiles subtle distressed edges and irregularities, replicating a hand-made tile aesthetic.

The evolution of this popular tile allows a unique, hand-made look, yet with all the benefits and cost effectiveness of a machine-made tile.

The Ashdowne range is fully compatible with the Marley full roof system, complemented by a range of fittings and accessories, and covered by a 15-year guarantee.



COLOUR AVAILABILITY




TECHNICAL DATA

Size of tile	265mm x 165mm	
Minimum pitch*	35°	
Maximum pitch	90°	
Minimum headlap	Roof	65mm
	Vertical	35mm
Maximum gauge	Roof	100mm
	Vertical	115mm
Tile thickness	11mm (nominal)	
Cover width	165mm (nominal)	
Covering capacity (net)	Roof	60 tiles/m ² at 100mm gauge
	Vertical	53 tiles/m ² at 115mm gauge
Weight of tiling (approx.)	Roof	65kg/m ² (0.64 kN/m ²) at 100mm gauge
	Vertical	57kg/m ² (0.56 kN/m ²) at 115mm gauge
Battens required (net)	Roof	10.0 lin.m/m ² at 100mm gauge
	Vertical	8.7 lin.m/m ² at 115mm gauge
Batten size recommended (fixed to BS 5534)	38 x 25mm for rafters/supports not exceeding 600mm centres	
Tile nails	38mm x 2.65mm	
Authority	BS EN 1304	

* The minimum recommended pitch and lap may be influenced by special circumstances, please contact the Technical Advisory Service for further information.

PRODUCT INFORMATION

Tile camber
Single camber



Feature tiles

Available in a range of colours. For advice on the use of feature tiles in main roof areas, contact the Technical Advisory Service.



Bullnose



Club

SUSTAINABILITY

Green guide rating**	A+
BES 6001	Excellent

** Element Ref: 812410006

Tell me more

Call 01283 722588

Email info@marley.co.uk

Or visit marley.co.uk/ashdowne

Marley, Lichfield Road, Branston, Burton upon Trent, DE14 3HD

