

# Kingston Handmade

## Restoration Red Imperial



**Ibstock**  
At the heart of building



### Product Information

Ibstock Code:	4354
Type:	Handmade
Facing Description:	Sandcreased
Dry Brick Weight (kg):	2.9kg
Pack Quantity:	420
Packaging (standard):	Shrinkwrapped On Pallets(wood)
Factory:	Swanage

### Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	228x109x68
Size Tolerances Mean & Range:	T1 R1
Configuration:	Single Frog
Voids (%):	7-12
Compressive Strength (N/mm <sup>2</sup> ):	15
Active Soluble Salts:	S2
Water Absorption (% weight):	13
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m <sup>3</sup> ):	1650
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m <sup>2</sup> /min):	Refer to Ibstock
EAN:	5036335044735