

TREVOR BALDWIN
WINDOWS DOORS AND CONSERVATORIES

49 Skeyton Road
North Walsham
Norfolk

08/06/2021

Dear Denise

As per your request, please find attached below my suppliers specification in support of your planning application for replacement windows to the farmhouse on the front elevation.

The vertical sliding sash windows are made by Rehau

Specification

Smooth White 137 mm front to back profile

Welded sashes

A Energy Rated

24 mm softcoat glass sealed units

Black SwissSpacer- Argon filled

Astragal Bars

The measurements for the windows are attached below:-

Done

Q2106950.pdf



Quote No: Q2106950
Ref:

Account: B2140
Ordered: 02 Jun 21
Required:

System: S719 New Heritage R

Location	Picture	Description	
Window 1		1380x1330 Window (Style 701) 149mm Cill Slim/Int (Welded) Reinforce for A Rate Heritage Sash Horns Pair (NOT Run Thru) Price includes Glass Surcharge Tilt Restrictor 350mm (Both Sashes) V/S Furniture White Over 800 0.675m ² : Price includes White Astragal Grid	
Window 2		980x1330 Window (Style 701) 149mm Cill Slim/Int (Welded) Reinforce for A Rate Heritage Sash Horns Pair (NOT Run Thru) Price includes Glass Surcharge Tilt Restrictor 350mm (Both Sashes) V/S Furniture White Over 800 0.452m ² : Price includes White Astragal Grid	
Window 3		1380x1530 Window (Style 701) 149mm Cill Slim/Int (Welded) Reinforce for A Rate Heritage Sash Horns Pair (NOT Run Thru) Price includes Glass Surcharge Tilt Restrictor 350mm (Both Sashes) V/S Furniture White Over 800 0.796m ² : Price includes White Astragal Grid	

