

Our fleet – equipment specifications

REEFER CONTAINERS

20' Standard Reefer

Description	Non-metric	Metric
Maximum payload	60,600 lb	27,490 kg
Dimensions	20' x 8' x 8'6"	20' x 8' x 8'6"
Volume	953 cubic feet	27 m ³
Door openings, width	7' 6 1/8"	2,290 mm
Door openings, height	7' 3 1/16"	2,212 mm
Internal, length	17' 10 9/16"	5,451 mm
Internal, width	7' 6 1/8"	2,290 mm
Internal, height to load line	7' 1 5/16"	2,167 mm
Weight, gross	67,200 lb	30,480 kg
Weight, tare	6,591 lb	2,990 kg



40' High Cube Standard Reefer

Description	Non-metric	Metric
Maximum payload	64,992 lb	29,480 kg
Dimensions	40' x 8' x 9'6"	40' x 8' x 9'6"
Volume	2,384 cubic feet	67.5 m ³
Door openings, width	7' 5 9/16"	2,276 mm
Door openings, height	8' 1 1/14"	2,471 mm
Internal, length	37' 11 7/8"	11,580 mm
Internal, width	7' 11 1/6"	2,275 mm
Internal, height to load line	7' 11 1/6"	2,415 mm
Weight, gross	74,957 lb	34,000 kg
Weight, tare	9,965 lb	4,520 kg



40' High Cube Starfresh

Description	Non-metric	Metric
Maximum payload	64,992 lb	29,400 kg
Dimensions	40' x 8' x 9'6"	40' x 8' x 9'6"
Volume	2,261 cubic feet	64 m ³
Door openings, width	7' 5 11/16"	2,278 mm
Door openings, height	8' 1 5/16"	2,473 mm
Internal, length	37' 11 13/16"	11,578 mm
Internal, width	7' 5 3/4"	2,280 mm
Internal, height to load line	7' 11 7/16"	2,425 mm
Weight, gross	74,957 lb	34,000 kg
Weight, tare	10,140 lb	4,600 kg

