



John Chambers Heritage Coastal Areas 80% Grass Seed Wildflower Mix  
Sown at a rate of 500g/100m<sup>2</sup> to supplier's specification.

The site should be weed free. Annual weeds should be controlled by mechanical means or by the use of contact based herbicide. Perennial weeds, for example docks thistle, nettles and couch grass can be dealt with using a translocated herbicide such as Round-Up. Cultivate to achieve a fine seed bed, sow seed mix and then roll to ensure firmness. The best results are obtained when there is good contact between the soil and the seeds.


Mix comprises:  
Low Maintenance Grass Seed, Wild Parsnip, Common Knapweed, Wild Carrot, Common Evening Primrose, Kidney Vetch, Common Bird's-foot-trefoil, Vipers Bugloss, Lady's Bedstraw, Oxeye Daisy, Bladder Campion, Cat's Ear, Hound's Tongue, Greater Knapweed, Ribwort Plantain, Foxglove, Sea Plantain, Sea Campion, Common St. John's Wort, Common Toadflax, Common Centaury, Tansy, Thrift, Harebell, Wild Thyme



Grass areas maintained close-mown along paths and around buildings for security and ease of maintenance



Wildflower grass areas allowed to flower. Mown twice in summer and late autumn. Cuttings removed from site



Hedgerow  
Following species planted in double staggered rows, 500mm between rows and 500mm between plants in the rows. Planted in the first planting season after construction. Protected with mulch mats and Tubex tree shelters. All to be 300-450mm bare-rooted transplants, except for the Ilex which should be 3L pot-grown specimens

340no.	Crataegus monogyna	Hawthorn
100no.	Prunus spinosa	Blackthorn
100no.	Acer campestre	Field Maple
50no.	Corylus avellana	Hazel
20 no.	Ilex aquifolium	Holly
40no.	Malus sylvestris	Wild Apple
30no.	Euonymus europeaus	Spindle



Block planting of Sea Buckthorn, Hippophae rhamnoides and Pyracantha 'Orange Glow' in single-species groups of 7-15 2L pot-grown plants, 40-60cm high, at 1.5 metre spacing.



Specimen planting of Pinus nigra, 125-150cm, Leader with laterals, 3x, Rootballed.

Footpaths to have a tar/spray rolled gravel finish