



## ATALEDB/1000



### Features

Robust die-cast aluminium bollard with a textured graphite finish.

Die-cast aluminium head with polycarbonate lens.

Comparable performance to 70W HQI.

Powered by Philips.

Integral emergency option.

Supplied c/w root mounting kit.

LED lifespan L70 50,000 hours.

Non-dimmable.

## General Information

Lamp Type	LED
Colour / Finish	Graphite
IP Rating	IP66
Class Protection	1
Internal / External	External
Surface / Recessed / Suspended	Surface
Warranty (Years)	5
CE Mark	Yes
Width (mm)	202
Height (mm)	1000

## Technical Information

Wattage	25W
Lumens Delivered	2390lm
Lm/W	96lm
CRI	Ra 70
CCT	4000K
Input	230V
Hertz	50/60Hz
Operating Temp	-25°C to 50°C

Datasheet generated from <https://onetimepim.com> last updated Tuesday, March 30, 2021 8:29:53 AM

