



EXTERNAL WALL BUILDUP:

- CEDRAL CLADDING WHERE SHOWN
- EXTERNAL RENDER WHERE SHOWN
- 100mm BLOCKWORK
- 50mm CAVITY
- 75mm INSULATION
- 100mm BLOCKWORK
- 13mm PLASTERBOARD AND SKIM

PARTITION WALL BUILDUP:

- 100mm SWD STUDWORK AT MAX 400mm CENTRES WITH NOGGINS AS APPROPRIATE AND AT EVERY BUTT JOINT OF PLASTERBOARD
- 13mm PLASTERBOARD AND SKIM BOTH SIDES

WINDOWS:

- ALUMINIUM FRAMED DOUBLE GLAZED, ARGON FILLED UNITS TBC WHEN SUPPLIER IS SELECTED

DOORS:

- EXTERNAL DOORS TO BE ALUMINIUM FRAME UNITS TO MATCH WINDOWS
- INTERNAL DOORS TO BE TIMBER (PATTERN TO BE AGREED) WITH FIRE RESISTANCES AS REQUIRED

REV	DESCRIPTION	DATE	INS
C	SIDE DOOR CHANGED TO WINDOW	15/12/2020	JH
B	ANNOTATED	13/10/2020	JH
A	PREVIOUS PLANS SUPERSEDED, DESIGN REVIEWED	16/01/2020	JH

Stackhouse Design
Barbican House, 36 New Street, Barbican, Plymouth, Devon, PL1 2NA
Tel: 01752 426 400
info@stackhousedesign.co.uk
www.stackhousedesign.co.uk

TITLE	AUTHOR
PROPOSED NEW BUILD No.3 MORLEY COTTAGES BORRINGTON HILL, PLYMOUTH, PL7 4DH	JH
CLIENT	DATE
MARK HINCHLIFFE	16/01/2020
DETAIL	SCALE
PROPOSED LOWER FLOOR PLANS	1:100 @ A3
	CHECKED

STATUS	DRAWING No.	REVISION
PLANNING	17-02-10	C