

Specification - Flexible faced lightbox units with 200mm return depth, all external surfaces powder coated to satin RAL colour reference. Complete with digitally printed, Ultralon tensioned Pvc face panel to agreed design. Unit fitted to existing aluminium cladding panels and carrier rails using self tapping hex headed bolts through internal support frame. Additional support provided via threaded stud fixings penetrating through the cladding and Unistrut support structure using threaded bolts with nuts and anti-vibration washers. Penetrations to be silicone sealed to prevent water ingress.

