



**Foul Drainage**  
 Connection to main drainage is not available therefore a Harlequin Hydroclear 6 person Sewage Treatment Plant is to be installed with a 77.0m long drainage field with 0.6m wide trench. drainage field are to be installed and construction in a looped system in compliance with BS 6297:2007+A1:2008.

Drainage field discharge point is 200.0m+ from any other private discharge point and 50m+ away from any SAC or watercourse. The daily discharge volume will be 0.75m<sup>3</sup> based on 1 2 bedroom house.

Site Area. 293 m<sup>2</sup>

North.



Dwg Notes.

Do not scale, use figured dims only. Dims displayed in millimeters unless stated otherwise. All dimensions to check on site prior to commencement, any discrepancies to be report to designer.

This drawing is COPYRIGHT. Drawing must not be reproduced for any purpose without written permission.

**SBA**rchitecture

Design, Planning, Building Regs.

E - sambarchitecture@gmail.com

T - 07720225585

Project.

PROPOSED BARN CONVERSION,  
 HORNBY, LLANDINAM, SY175BQ

Subject.

PROPOSED LOCATION PLAN

Scale.

1:2500 @ A3

0 50 100

Date.

05 / 2021

Ref.

0035 / BP / 2