## SCHEDULE OF PLANNING CONDITIONS Ref; -AJJ/CVB/2021

# LAND ADJACENT TO BYLANES, COALPIT LANE, STOKE ST MICHEAL, SHEPTON MALLET, SOMERSET BA3 5JT

OUTLINE APPROVAL 2018/2573/OTS, 2019/3036/REM(PLOT1), 2020/0678/REM(PLOT2)

#### Planning condition 3. Hard and soft Landscaping (Pre-occupation) Plots 1& 2

## Schedule of species to be read in conjunction with plan Ref; -CLMS/101/A

	Species	height (M)
1	Amelanchmier 'lamarki"	6
2	California lilac tree	1.2
3	Filigree purple acer	4
4	Magnolia Rustica Rubra	2
5	Flaming willow	2
6	Hydranga 'Limelight'	1-1.2
7	Topiary bay tree	2
8	Shrubs and decorative grasses	.4-1.5
9	Native hedge mixes	1.2
10	Prunus 'pink shell'	4
11	Sorbus 'Eastern promise'	8
12	Acer griseum	8-12
13	Retained fencing and hedges	
14	Existing Hollytree	4
15	Apple-Sunset AGM	4
16	Peach-peregrine	4
17	Pear-conference	4
18	Plum-opal AGM	4.5
19	Apple - Peasegood non such	4
20	Lawn	

#### Drive

50 mm golden self-binding gravel over a sub-base of 75mm well compacted type 1 hardcore on geotechnical membrane.

½ round light grey precast kerb edgings

Drive entrance tarmacadam 60mm base coat 20mm topcoat

Fit Atco channel drain between tarmac and drive.

#### **Paths and Patios**

Grey Indian sandstone

## <u>Implementation</u>

Prior to occupation -driveway, parking and external paths/patios.

12 months following occupation-hedging tress decorative shrubs/grasses and lawns.

Planning condition 4 Parking (Be-spoke trigger) -Plots 1 & 2

The parking area will be as shown on plan CLSM/101/A. sufficient parking for four cars will be provided on each drive.

## Planning condition 5 External lighting (Bespoke Trigger) – Plots 1 &2

The position of all external lighting is shown on Plan CMSM/101/A it is proposed to use the light fitting specified below; -



Massive Boston Outdoor Wall Light with Motion Sensor PIR - Black (Requires 1 x 60W E27 Bulb)

## Planning condition 6 Removal of hedgerows (Bespoke Trigger) - Plots 1 & 2

## **Accommodation works**

The existing hedge was removed at the commencement of work in Feb 2020 any further work to complete site access will be carried out between 1/9/21 and 28/2/22.

14<sup>TH</sup> July 2021