



PLANTING SCHEDULE

Individual Native Trees			
Species	Description	Height/Girth	
Quercus robur (Pendunculate Oak)	Standard	2500-3000mm/8-10cm	
Quercus petraea (Sessile Oak)	Standard	2500-3000mm/8-10cm	
Acer campestre (Field Maple)	Standard	2500-3000mm/8-10cm	
Salix pentandra (Bay Willow)	Feathered	2000-2500mm	
Native Hedgerow Mix			
Species	Percentage	Size	Spacing
Crataegus monogyna (Hawthorn)	70	400-600mm/1+1	5/lin m
Corylus avellane (Hazel)	20	400-600mm/1+1	5/lin m
Prunus spinosa (Blackthorn)	5	400-600mm/1+1	5/lin m
Ilex auifolium (Holly)	5	400-600mm/2L pot	5/lin m
Acer campestre (Field Maple)	5	400-600mm/1+1	5/lin m

PLANTS AND PLANTING

All plants and planting to comply with the requirement of all current/relevant British Standard Specifications including BS3936: Parts 1 & 4 (Nursery Stock) and BS4428:1989 (General Landscape Operations). All planting to be carried out within the recognised planting season (November to March). All to be British Grown stock and fully hardened off. All native species to be of local origin.

Root Dip
Proprietary root dip applied to all bare-rooted stock (1) at time of lifting at nursery and (2) prior to planting.

Watering
Thoroughly water-in all new plants immediately after planting.

Tree Stakes and Ties
Stakes – to be pressure treated, round, smooth and peeled Larch or Chestnut, not less than 100mm diameter. Use proprietary tree ties applied in accordance with manufacturer's recommendations.

Hedgerow Planting
Hedging plants to be planted in trenches wide enough to allow for full root spread. Set out plants as scheduled in a double staggered row using a total of 5 plants per linear metre. Rows to be set 450mm apart.

Tree & Shrub Protection
All newly planted stock to be fully protected from rabbit damage by the use of proprietary tree/shrub guards applied in accordance with the manufacturer's recommendations. All newly planted stock to be fully protected from browsing livestock, where applicable by the installation of permanent stockproof fencing. Rabbit proof fencing may be used as an alternative to individual tree guards.

TIMETABLE
All new planting and seeding to be completed within 12 months of completion of development.

LANDSCAPE MAINTENANCE & MANAGEMENT

Trees and hedgerows
Regular visits (Years 1-5) required to maintain all newly planted stock in a weed free condition. A 30cm wide strip along each side of the hedges and a 1m diameter ring around each individual plant is to be maintained in a weed free condition using a combination of repeated applications of an approved translocated systemic herbicide during the growing season followed by an approved residual herbicide application during late winter/early spring.

Planting generally
Any plants affected by frost heave or wind rock shall be re-firmed. Protective fencing, stakes, ties and tree guards are to be checked at each visit and adjusted, repaired or replaced as necessary to maintain healthy growth.

Hedgerow trimming:
In the second or third year new hedging plants should be hand trimmed to an even height of approximately 750mm to encourage side shoots and the development of a sound base to the hedge. For the following two or three years, the leaders should be allowed to grow unhindered and the sides lightly trimmed only if necessary. After the first 5 years, mechanical hedge trimming can commence with hedges being cut every three years back to a height of approximately 3.0m. Hedge cutting operations should be programmed to avoid the bird nesting season (March to July) as it is an offence to harm nesting wild birds. Care should be taken to avoid damage to hedgerow trees and these should be tagged to make them more obvious to the hedge trimming operator.

Replacement Planting
Any tree/shrub losses to be replaced annually (Years 1-5) in accordance with original planting schedule and specification.

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELATED DRAWINGS. ALL DIMENSIONS MUST BE CHECKED AND VERIFIED ON SITE BEFORE COMMENCING ANY WORK OR PRODUCING SHOP DRAWINGS. THE ORIGINATOR SHOULD BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCY. THIS DRAWING IS COPYRIGHT AND REMAINS THE PROPERTY OF ROGER PARRY & PARTNERS.

..... Footpath
All existing trees and hedgerows to be retained.

Rev	Description	Date	Dr by	App by
Original				



Residential - Agricultural - Commercial	
Job	Agricultural Building
Title	Landscaping Plan
Location	The Gear Meifod Powys SY22 6XX
Client	Mr D Langford
Scales	1:1250 @ A3
Drawing No.	RB-MZ308-06
Drawn by	AZ
Date	21/07/2021

HOGSTOW HALL, MINSTERLEY
SHREWSBURY, SHROPSHIRE. SY5 0HZ
Tel: 01743 791336 Fax: 01743 792770
email: mail@rogerparry.net
Web address: www.rogerparry.net
Roger Parry & Partners LLP Partnership no OC132503
Registered in England and Wales, Shrewsbury, Shropshire, SY5 0HZ
A list of members of the LLP is available at the above address.