

Type	Name	Age	DBH	Height	1stB	N	E	S	W	Cond	Life Exp	Comments	Recommendations / development	RPR m	RPA m <sup>2</sup>	Category
H1	Acer pseudoplatanus (Sycamore), Ilex aquifolium (Holly), Crataegus monogyna (Hawthorn), Sambucus nigra (Elder), Prunus spinosa (Blackthorn)	M	120	2	0.5	0.5	0.5	0.5	0.5	Fair	20+	Field boundary hedge, evidence of historic laying, flail trimmed. Colonisation by Elderberry and even aged profile leading to formation of gaps in hedge structure		1.44	6.52	C2
H2	Ilex aquifolium (Holly)	M	120	2.5	0	0.5	0.5	0.5	0.5	Good	20+	Maintained garden boundary hedge		1.44	6.52	C2
T1	Fagus sylvatica (Beech)	EM	500	14	4	7	7	7	7	Good	20+	Off site tree in adjacent garden (DBH estimated) previous crown lifting on site side of tree		6	113.11	B2
T2	Prunus (Ornamental Flowering Cherry)	M	600	12	5	6	6	6	6	Fair	20+	Off site tree in adjacent garden (DBH estimated) previous crown lifting on site side of tree		7.2	162.88	B2
G1	Betula pendula (Silver Birch), Aesculus hippocastanum (Horse Chestnut), Larix decidua (European Larch), Prunus avium (Wild Cherry), X Cupressocyparis leylandii (Leyland Cyp)	EM	300	12	3	6.5	6.5	6.5	6.5	Good	20+	Off site group in adjacent garden (DBH estimated) previous crown lifting Silver Birch to 4m on site side. Interdependent growth forms due to density of group. Leylandii along edge are dense and multi stemmed		3.6	40.72	B2
H3	Crataegus monogyna (Hawthorn)	EM	100	2.5	0	0.5	0.5	0.5	0.5	Fair	20+	Relatively recently planted garden boundary hedge		1.2	4.52	C2
H4	Crataegus monogyna (Hawthorn)	EM	100	1.5	0	1	1	1	1	Fair	20+	Planted filed boundary hedge, has not been laid		1.2	4.52	C2
T3	Picea abies (Norway Spruce)	EM	490	11	1.5	4	4	4	4	Fair	10+	Tree located adjacent to H4, balanced form, 2x stub cut low branches on site side of tree		5.88	108.63	C1
G2	Fraxinus excelsior (Ash), Crataegus monogyna (Hawthorn)	EM	120	5	1	1.5	1.5	1.5	1.5	Fair	10+	Appears to be group that was planted as a hedge but has not been maintained as one. Now a spindly linear grouping		1.44	6.52	C2
H5	Crataegus monogyna (Hawthorn)	EM	120	2	0	0.5	0.5	0.5	0.5	Fair	20+	No access due to waterlogging of lower site, appears to be maintained at a low height		1.44	6.52	C2
G3	Betula pendula (Silver Birch), Prunus avium (Wild Cherry)	EM	200	12	2	4	4	4	4	Good	10+	Group in area adjacent o highway verge at end of H1. 2 x Birch and 1 x Cherry, interdependent, close spaced forms (DBH estimated due to dense undergrowth)		2.4	18.1	C2
T4	Acer pseudoplatanus (Sycamore)	M	550	13	3	5.5	5.5	5.5	5.5	Good	20+	Located at edge of watercourse with root restriction to NE from stream. Ivy cover on stem and crown, no access due to waterlogging (DBH estimated)		6.6	136.87	B2
T5	Quercus petraea (Sessile Oak)	M	800	13	3	9	9	9	9	Good	40+	Off site tree located at far side of highway and watercourse, no root development towards site (DBH estimated - no access to stem)		9.6	289.57	A2
T6	Acer pseudoplatanus (Sycamore)	M	700	13	4.5	8	8	8	8	Good	40+	Off site tree located at far side of highway and watercourse, no root development towards site (DBH estimated - no access to stem)		8.4	221.7	A2