

PLA-ZM R32

4-Way Blow Ceiling Cassette System

Power Inverter Heat Pump (Single Phase)

Mr.SLIM™

The **PLA-ZM Power Inverter range** is a ceiling cassette system that blends a host of outstanding features with a sophisticated streamlined design. Offering high seasonal efficiency, advanced control options and extended pipe runs, this range is extremely flexible.

R32



Key Features & Benefits:

- Improved airflow control, including horizontal airflow for greater comfort
- Optional 3D i-see sensor grille (PLP-6EAE) provides customised comfort by automatically monitoring room occupancy, position and body temperatures
- Optional filter lowering operation down to 4m (PLP-6EAJ)
- Full heating capacity down to -3°C
- 100m pipe run (Size 100-140)
- Replace Technology available



R32


POWER INVERTER



PLA-ZM INDOOR UNITS		PLA-ZM35EA	PLA-ZM50EA	PLA-ZM60EA	PLA-ZM71EA	PLA-ZM100EA	PLA-ZM125EA	PLA-ZM140EA
CAPACITY (kW)	Heating (nominal)	4.1 (1.5-5.2)	6.0 (2.5-7.3)	7.0 (2.8-8.2)	8.0 (3.5-10.2)	11.2 (4.5-14.0)	14.0 (5.9-16.0)	16.0 (5.7-18.0)
	Cooling (nominal)	3.6 (1.5-4.5)	5.0 (2.3-5.8)	6.1 (2.7-6.5)	7.1 (3.3-8.1)	9.5 (4.9-11.4)	12.5 (5.5-14.0)	13.4 (6.2-15.0)
	Heating (30°C)	3.5 (1.35-4.4)	5.1 (2.15-6.2)	6.0 (2.38-6.97)	6.8 (3.0-8.65)	9.5 (3.85-11.9)	11.9 (4.25-13.6)	13.6 (4.85-15.3)
	Cooling (30°C)	3.3 (1.45-4.15)	4.6 (2.1-5.15)	5.6 (2.48-5.98)	6.55 (2.95-7.45)	8.2 (4.5-10.5)	11.5 (5.05-12.3)	12.9 (5.7-14.1)
SHF (nominal)	0.95	0.85	0.77	0.72	0.77	0.70	0.70	0.70
COP / EER (nominal)	5.00 / 5.10	4.40 / 4.52	4.10 / 4.20	4.40 / 4.30	4.30 / 4.60	3.81 / 3.70	3.71 / 3.55	3.71 / 3.55
SCOP (nsh) / SEER (nsc) (BS EN14825)	4.70 / 7.50	4.90 / 7.80	4.80 / 7.20	4.80 / 7.80	4.80 / 7.70	4.70 (1.85 %)	4.60 (2.03 %)	4.60 (1.81 %)
ErP ENERGY EFFICIENCY CLASS	Heating/Cooling	A++ / A++	A+ / A++	A++ / A++	A++ / A++	A++ / A++	-	-
AIRFLOW (l/s)	Lo-M-M2-H	183-217-250-267	200-233-267-300	200-235-267-300	283-317-350-383	317-367-417-467	350-400-433-485	400-433-485-533
PIPE SIZE mm (in)	Gas / Liquid	12.7 (1/2) / 6.35 (1/4")	12.7 (1/2) / 6.35 (1/4")	15.88 (5/8") / 9.52 (3/8")	15.88 (5/8") / 9.52 (3/8")	15.88 (5/8") / 9.52 (3/8")	15.88 (5/8") / 9.52 (3/8")	15.88 (5/8") / 9.52 (3/8")
SOUND PRESSURE LEVEL (dBA)	Lo-M-M2-H	26-28-29-31	27-29-31-32	27-29-31-32	28-30-33-36	31-34-37-40	33-36-39-41	36-39-42-44
SOUND POWER LEVEL (dBA)		51	54	54	57	61	62	65
DIMENSIONS (mm)	Width x Depth x Height (Gross)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)	840 (850) x 840 (850) x 258 (40)
WEIGHT (kg)	Unit / Grite	21 / 5	21 / 5	21 / 5	24 / 5	26 / 5	26 / 5	28 / 5
ELECTRICAL SUPPLY		Fed by Outdoor Unit	Fed by Outdoor Unit	Fed by Outdoor Unit	Fed by Outdoor Unit	Fed by Outdoor Unit	Fed by Outdoor Unit	Fed by Outdoor Unit
FUSE RATING (BS88) - HRC (A)		6	6	6	6	6	6	6
INTERCONNECTING CABLE No. CORES		4	4	4	4	4	4	4
GRILLE REFERENCE		P/P-SEA	P/P-SEA	P/P-SEA	P/P-SEA	P/P-SEA	P/P-SEA	P/P-SEA
WIRED REMOTE CONTROLLER REFERENCE		PWR-40MAA	PWR-40MAA	PWR-40MAA	PWR-40MAA	PWR-40MAA	PWR-40MAA	PWR-40MAA
WIRELESS REMOTE CONTROLLER REFERENCE		PWR-SL100A-E	PWR-SL100A-E	PWR-SL100A-E	PWR-SL100A-E	PWR-SL100A-E	PWR-SL100A-E	PWR-SL100A-E

PUZ-ZM OUTDOOR UNITS		PUZ-ZM35VKA	PUZ-ZM50VKA	PUZ-ZM60VHA	PUZ-ZM71VHAR1	PUZ-ZM100VKAR1	PUZ-ZM125VKAR2	PUZ-ZM140VKAR2
SOUND PRESSURE LEVEL (dBA)	Heating/Cooling	46 / 44	46 / 44	49 / 47	49 / 47	51 / 49	52 / 50	52 / 50
SOUND POWER LEVEL (dBA)	Cooling	65	65	67	67	69	70	70
WEIGHT (kg)		46	46	70	70	116	116	116
DIMENSIONS (mm)	Width x Depth x Height	809 x 300 x 630	809 x 300 x 630	950 x 330 x 25 x 943	950 x 330 x 25 x 943	1050 x 330 x 40 x 1336	1050 x 330 x 40 x 1336	1050 x 330 x 40 x 1336
ELECTRICAL SUPPLY		220-240V, 50Hz	220-240V, 50Hz	220-240V, 50Hz	220-240V, 50Hz	220-240V, 50Hz	220-240V, 50Hz	220-240V, 50Hz
PHASE		Single	Single	Single	Single	Single	Single	Single
SYSTEM POWER INPUT (kW)	Heating/Cooling (nominal)	0.820 / 0.705	1.363 / 1.106	1.707 / 1.452	1.818 / 1.651	2.804 / 2.065	3.674 / 3.378	4.312 / 3.772
	Heating/Cooling (30°C)	0.73 / 0.59	1.21 / 0.94	1.43 / 1.15	1.61 / 1.39	2.09 / 1.77	3.27 / 2.67	3.83 / 3.15
STARTING CURRENT (A)		5.0	5.0	6.0	6.0	13.0	13.0	13.0
SYSTEM RUNNING CURRENT (A)	Heating/Cooling (MAX)	3.89 / 3.51 (13.2)	6.05 / 5.00 (13.2)	7.39 / 6.31 (19.3)	7.79 / 7.06 (19.3)	11.25 / 8.97 (27.0)	15.77 / 14.53 (27.0)	18.41 / 15.88 (28.7)
FUSE RATING (BS88) - HRC (A)		16	16	25	25	32	32	40
MAINS CABLE No. CORES		3	3	3	3	3	3	3
MAX PIPE LENGTH (m)		50	50	55	55	100	100	100
MAX HEIGHT DIFFERENCE (m)		30	30	30	30	30	30	30
CHARGE REFRIGERANT (kg) / (CO ₂ EQUIVALENT (t) - R32 (GWP 675) - 30m)		2.0 / 1.35	2.00 / 1.35	2.90 / 1.89	2.80 / 1.89	4.00 / 2.70	4.00 / 2.70	4.00 / 2.70
MAX ADDITIONAL REFRIGERANT (kg) / (CO ₂ EQUIVALENT (t) - R32 (GWP 675)		0.30 / 0.20	0.30 / 0.20	0.80 / 0.54	0.80 / 0.54	2.80 / 1.89	2.80 / 1.89	2.80 / 1.89

PLA-ZM35/50/60/71/100/125/140EA DIMENSIONS



UNITED KINGDOM Mitsubishi Electric Europe Living Environment Systems Division, Travellers Lane, Hatfield, Hertfordshire, AL10 8XB, England
 IRELAND Mitsubishi Electric Europe, Westgate Business Park, Ballymount, Dublin 24, Ireland

Country of origin: United Kingdom - Japan - Thailand - Malaysia. ©Mitsubishi Electric Europe 2020. Mitsubishi and Mitsubishi Electric are trademarks of Mitsubishi Electric Europe B.V. The company reserves the right to make any variation in technical specification to the equipment described, or to withdraw or replace products without prior notification or public announcement. Mitsubishi Electric is constantly developing and improving its products. All descriptions, illustrations, drawings and specifications in this publication present only general particulars and shall not form part of any contract. All goods are supplied subject to the Company's General Conditions of Sale, a copy of which is available on request. Third-party product and brand names may be trademarks or registered trademarks of their respective owners.

Note: The fuse rating is for guidance only. Please refer to the relevant databook for detailed specification. It is the responsibility of a qualified electrician/electrical engineer to select the correct cable size and fuse rating based on current regulation and site specific conditions. Mitsubishi Electric's air conditioning equipment and heat pump systems contain a fluorinated greenhouse gas, R410A (GWP:2088, R32 (GWP:675), R407C (GWP:1774), R134a (GWP:1430), R513A (GWP:631), R454B (GWP:468), R1234ze (GWP:7) or R1234yf (GWP:4). These GWP values are based on Regulation (EU) No 517/2014 from IPCC 4th edition. In case of Regulation (EU) No 625/2011 from IPCC 3rd edition, these are as follows: R410A (GWP:1975), R32 (GWP:593), R407C (GWP:1653) or R134a (GWP:1300).

Effective as of May 2020

