



INSTALL NEW BLOCKWORK TO EXISTING WINDOW. REVISE DOOR TO LEAVE GAP AT BOTTOM TO REPLACE AIR REMOVED BY THE EXTRACTOR FAN (REVISE FAN TO INCLUDE DUCTING TO EXTERIOR).

EXISTING CONSTRUCTION SHADED
 REMOVE EXISTING INSPECTION CHAMBER*. INSTALL NEW SHALLOW ACCESS CHAMBER A IN GARDEN WITH NEW 100mm DRAIN TO EXISTING DRAIN. FINAL DETAILS TO BE AGREED ON SITE.

* INVERT 600mm.

INSTALL STAINLESS STEEL PROFILE AT EXTG/NEW WALL JUNCTIONS.

INSTALL LINTEL(S) OVER DRAIN RUN LINE OF ROOFLIGHT OVER.

225mm MIN STEP OUTSIDE DOORS.

PWP TO TRAPPED GULLY. 100mm DIA DRAIN FALLING 1 in 40 TO NEW SOAPWAY MIN 5M FROM BLDG (SEE SPECIFICATION)

36 WESTBROOKE ROAD SIDCUP DA15 7PH

SINGLE STOREY REAR EXTENSION

DRAWING No AM/1718/7/4

PROPOSED GROUND FLOOR PLAN

DATE JUNE 2017 SCALE 1:50

