



Symbol	Qty	Label	Lum. Lumens	LLF	Description
	15	A-EM	812	0.900	6w LED Semita Urban bulkhead with flood optic Building Mounted at 3m
	10	B-EM	802	0.900	6w LED Semita Urban bulkhead with cycle optic Building Mounted at 3m
	15	C-EM	1570	0.900	11,1w LED Semita Urban bulkhead with cycle optic Building Mounted at 3m
	12	D	3220	0.900	31w (2 module) S25ma ECO RAYS S with S Optic Column Mounted at 4m

Label	Units	Avg	Max	Min	Uniformity
Block 1 Perimeter	Lux	28.32	47	14	0.49
Block 2 Perimeter	Lux	29.93	54	16	0.53
Block 3 Perimeter	Lux	28.73	41	17	0.59
Central Walkway	Lux	29.27	43	14	0.48
Left Courtyard	Lux	26.43	46	11	0.42
Top Pathway & Right Courtyard	Lux	21.74	41	12	0.55

Unity Street Student Accommodation Bristol

Scale: 1:200 at A1 | Project Number: E43277

Date: 3 June 2021 | Drawing No.: 43277/PJ/A

Lighting Designer: Paul James

HEA **HEMSA** **IP** **IP** **IP**

For our LED lighting designs a 0.9mf has been used. If this differs from the maintenance period for this project then you must advise us accordingly.

A lighting applications design service is provided by us in good faith and without charge, relating to Kingfisher products only. As such, whilst every endeavor is made for accuracy from information provided by yourselves, the final responsibility for the suitability of the design lies with the client. The company cannot, therefore, accept any liability or consequential loss incurred.

A1