

CHANEL 173 New Bond Street - Proposed Lighting Fixtures

Spectra Flood Q15 Exterior Fixture

The LEDJ IP65 rated Spectra Q series bathes architectural details in constantly changing colours from its high output LEDs. The 45° beam angle smoothly washes in deep rich colours or warm pastel tones. The rugged aluminium exterior ensures years of use in most weather conditions while the integral mounting brackets complete the fixtures sleek, modern appearance. The OLED menu display with 4 button control panel facilitates control over colour mixing, colour fades, chases and DMX.

- 15 x 5W quad-colour LEDs (RGBW)
- Beam angle: 45°
- 1,746 Lux @ 2m (full on)
- 4kHz refresh rate
- DMX channels: 4/6 or 9 selectable
- RDM (Remote Device Management)
- Static colour, colour change, colour fade, auto and master/slave modes
- 0 - 100% dimming and variable strobe
- 4 button menu with OLED display
- IP rated power input/output trailing connections
- IP rated 3-Pin DMX input/output trailing connections

- Power consumption: 80W
- Power supply: 100~240V, 50/60Hz
- IP rating: IP65
- Dimensions: 207 x 330 x 110mm
- Weight: 5.2kg

