

**Application reference no: 21/00170/FUL**

**Address: Ladythorn, Cleeve Hill, Southam, Cheltenham, Gloucestershire, GL52 3QB**

**Re: Information and details relating to Conditions 5, 6 & 7.**

**Condition 5:** The proposed roofing and walling materials are as follows and as shown on the image below; -

- Walls: Syreford Quarry Cotswold stone
- Walls: Through colour render
- Roofing: Grey Iko polymeric single ply membrane or equivalent.
- Windows: Smart systems powder coated aluminium in RAL 7016

**Please find additional manufacturer information appended. Samples available on request**



**Condition 6:** The Syreford Quarry Cotswold stone will be laid in 75mm and 150mm courses with circa 10mm vertical and horizontal joints. The courses will be made up of a combination of the following approximate size stones;

- 229 x 65mm
- 305 x 65mm
- 380 x 65mm
- 229 x 140mm
- 305 x 140mm
- 380 x 140mm

**Condition 6 cont.....**

Please refer to image below. A sample panel will be constructed on site at request.



**Condition 7:** All windows and doors are to be RAL 7016 Smart Systems Powder coated aluminium and Smart Systems Visofold 1000 & 2000. Please refer to the manufacturers details appended.