



PLAN VIEW
scale: 1:100

EN01
01

Specification for eight lane enclosed 'tp365' system

Playing surface carpets

Overall ten lane dimensions: 38m x 29.2m
 'tp1' premium grade wilton woven synthetic playing surface carpets per lane: 27m x 3.65m Green with Blue borders
 Optional: single tone NPC or Green
 Optional: Green or NPC with Blue borders
 Optional: training aid - contrasting stump lines
 'tp5' premium grade tufted run up carpet per lane: 11m x 3.65m single tone green

Player transition area

'tp5' premium grade tufted rcarpet dimensions: 10m x 5m

Shock pads: per lane

'tp2' batting area: pace modifying shock pads for the pitching area 19m x 3.4m
 'tp3' bowling area and run-up: load absorbing shock pad 19m x 3.6m

Steelwork system dimensions: per lane

Height: 4m
 Lane length: 25.55m
 Overall length 38m
 Width: 3.6 - 3.65m
 48mm diameter galvanised steel tubes set in a 52mm diameter socket.
 Optional: powder coated steelwork green or black
 Optional: Pedestrian gate with latch

Netting systems

25.55m x 4m HD Protection tunnels: exclusive total-play design one seamless piece of total-play's 'HD' netting secured with PVC encapsulated tension wire
 12.45m x 4m HD panel sidewalls
 4m high white bowler netting
 Single batting curtains (white mesh) 2m x 7.3m
 Optional: green or black netting
 Optional: additional 'double' or 'wrap' batting curtains
 Optional: total-play's 'HD' netting in walled panel design
 Optional: protection skirt in green or black (PVC): protects the bottom section of netting, either 500m or 1m high.

Security fence

All systems can be built with perimeter security fencing and gates. design options include gate width, fence height, colour and type of perimeter safety path.