



**Job no:** 128  
**Date:** 03/09/2021  
**Assessor name:**  
**Registration no:** "As Built"  
**Development name:** Bishops Meadow,  
 Albany Farm,

WATER EFFICIENCY CALCULATOR FOR NEW DWELLINGS - (BASIC CALCULATOR)											
House Type:		AH2		A		B		Ca			
Description:		Plots 21, 33, 34		Plots 30, 31, 32, 35, 36		Plots 17, 18		Plots 45, 46, 47, 48			
Installation Type	Unit of measure	Capacity/flow rate	Litres/person/day	Capacity/flow rate	Litres/person/day	Capacity/flow rate	Litres/person/day	Capacity/flow rate	Litres/person/day		
Is a dual or single flush WC specified?		Dual		Dual		Dual		Dual			
WC	Full flush volume	6	8.76	6	8.76	6	8.76	6	8.76		
	Part flush volume	3	8.88	3	8.88	3	8.88	3	8.88		
Taps (excluding kitchen and external taps)		Flow rate (litres / minute)		5		9.48		5		9.48	
Are both a Bath & Shower Present?		Bath & Shower		Bath & Shower		Bath & Shower		Bath & Shower			
Bath	Capacity to overflow	156	17.16	156	17.16	156	17.16	156	17.16		
Shower	Flow rate (litres / minute)	8	34.96	8	34.96	8	34.96	8	34.96		
Kitchen sink taps		Flow rate (litres / minute)		8		13.88		8		13.88	
Has a washing machine been specified?		No		No		No		No			
Washing Machine	Litres / kg		17.16		17.16		17.16		17.16		
Has a dishwasher been specified?		No		No		No		No			
Dishwasher	Litres / place setting		4.50		4.50		4.50		4.50		
Has a waste disposal unit been specified?		No		No		No		No			
Water Softener	Litres / person / day		0.00		0.00		0.00		0.00		
Calculated Use		114.8		114.8		114.8		114.8			
Normalisation factor		0.91		0.91		0.91		0.91			
Total Consumption		104.4		104.4		104.4		104.4			
Code for Sustainable Homes Mandatory level		Level 3/4		Level 3/4		Level 3/4		Level 3/4			
External use		5.0		5.0		5.0		5.0			
Total Consumption		109.4		109.4		109.4		109.4			
17.K Compliance?		Yes		Yes		Yes		Yes			