



NOTES / LEGEND

Denotes refuse bin store

Driveway to be dense bitmac on consolidated type 1 on selected uphill compacted in 300mm maximum layers, 200 x 50mm P.C. flat top kerb edging, in situ concrete log, all laid to cross falls, existing access to be grubbed up, upfilled in type 1 as needed and new bitmac finish, include new ACO channel at heel kerb.

All levels to be checked on site before work starts.

Denotes external clothes dryer with slab access.

Barrier free access point to dwelling to front

ADR (Design) Ltd The Nurseries 5 Tak-Ma-Doon Road KILSYTH G65 0RS Telephone/Fax 01236 827749	
SITE PLAN	
Project Proposed New Detached House at Kelwinhead Road, Kelwinhead, G65 0QH. For Kelwinhead Projects Ltd.	Drawing 377/06
Date 08/19 Drawn By Dr	Job No. 377 Drawing No. 377/06 Rev.
Scale 1:500	