



Unit 82, Hillgrove Business Park, Nazeing Road, Nazeing, Essex, EN9 2HB

Telephone: 01992 890 88

Email: info@okeltd.co.uk

PROPOSAL OF WORKS

Dojo, Berkhamstead

1. Supply and fit 1 easy clean ventilation system. with Island Canopy size width 2600mm x depth 4300mm x height 520mm with removeable fire resistant baffle filters.
2. Service Spine to be cladded in high grade stainless steel for easy maintenance.
3. Ducting consists of 450 square high grade galvanised steel with access panels for cleaning, will be powder coated black.
4. Odour control, grease and smoke removal system ESP 2 Filter T2002 and the UV ozone control system.
5. Ducting to finish 1m above roof with jet cowl
6. Mixed flow acoustic lined turbofan cvat/4-900/500nd which has a DB rating of 52 and has been sized up on a face velocity of 0.35/ms airflow is 1.5m³/s at external pressure of 500 pa.g. .
7. Supply air system to be done by others.

All ducting and fan systems will be fitted with anti-vibration mounts big foots supports and brackets

MAINTENANCE

Recommended 6 monthly cleaning contract which includes maintenance on ventilation system, filters, ESP and UV ozone system, which will comply with rules and regulations for health and safety requiremnts

Subject to site survey