

3 (2)

MISTLEY CHURCH HALL REAR DOORS

**External Framed Ledged & Braced
Door 2032 mm x 813 mm x 44 mm**



Overview

This framed ledged and braced door is constructed of solid timber tongued and grooved boards, complete with exposed frame for greater stability. This is ideal for garden, outbuilding and utilitarian uses

- Doors are unfinished and require fully finishing on site to protect and prevent the ingress of moisture, which can cause warping.
- Does not include door furniture. Door furniture sold separately.
- A modern reproduction of the traditional cottage door, with an attractive boarded appearance with top and bottom rails

3 (2)

- A solid timber tongued and grooved door, complete with exposed frame, ledges and braces on the reverse side
- Can be trimmed up to a maximum of 12mm on any edge - any reduction should be removed evenly from each edge
- It is recommended that 3 hinges should be fitted to all doors weighing more than 20kg and doors where large differences of temperature or humidity on opposing faces can be expected. Recessed furniture and locks must not be placed within 76mm (3") of any r
- Supplied unfinished, seal and finish using at least 3 coats of a quality external paint or stain
- This is a natural timber product and variances in texture, colour and grain may be apparent.
- Door furniture sold separately.

Technical specification

Height	2032 mm	Thickness	44 mm
Width	813 mm	Door Height Imperial	6 ft 8 in
Door Thickness Imperial	1 3/4 in	Door Width Imperial	2 ft 8 in
Dimensions	2032 mm x 813 mm x 44 mm	Weight	19 kg
Material	Pine	Colour	Wood
Style	Gate	Finish	Pine Veneer
Opening Direction	Reversible	Construction	Mortice & Tenon
Treatment	Untreated	Lock Block	No
Certifications Met	FSC®	Type	Exterior Door
Made To Order	N	Brand Name	Plaut

Supplier Travis Perkins Ltd Colchester

Additional Works Door Frames and door furniture to be fitted

Doors to be painted white to match window frames and other exterior doors

Doors to be fitted by Rose Builders

3 (3)

MISTLEY CHURCH HALL COLLAPSIBLE BOLLARDS



Rhino Steel Fold Down Bollard

Diameter 60mm Height 615mm

Colour Yellow

Supplier Bollards Direct bollardsdirect.co.uk

Installation by Rose Builders :Two bollards to be installed across the entrance to the church hall to prevent vehicular access when hall not in use