

Max pitch 42 degrees

Ensure insulation is installed tightly between the rafters and over rafters to prevent thermal bridging

Ensure continuity of insulation

Eaves ventilator tray to ensure a 50mm ventilation gap

Cross ventilation to be provided by perpendicular eaves ventilation strip equivalent to a 25mm continuous gap at eaves level with insect grill and 50mm air gap between felt and insulation