



SAFETY DATA SHEET

Zinsser AllCoat® Exterior Matt

SECTION 1: Identification of the substance/mixture and of the company/undertaking

1.1 Product identifier

Product name : Zinsser AllCoat® Exterior Matt
Product description : Paint.
Product type : Liquid.

1.2 Relevant identified uses of the substance or mixture and uses advised against

Identified uses	
Industrial uses Consumer uses Professional uses	
Uses advised against	Reason
None identified.	-

1.3 Details of the supplier of the safety data sheet

William Zinsser (UK) Ltd.
 Portobello Industrial Estate
 Birtley
 County Durham
 United Kingdom
 DH3 2RE
 Telephone no.: +44 (0) 191 4106611
 Fax no.: +44 (0) 191 4920125
 enquiries@tor-coatings.com

e-mail address of person responsible for this SDS : rpmeurohas@ro-m.com

1.4 Emergency telephone number

Supplier

Telephone number : +44 (0) 207 858 1228
Hours of operation : 24 / 7

SECTION 2: Hazards identification

2.1 Classification of the substance or mixture

Product definition : Mixture

Classification according to Regulation (EC) No. 1272/2008 [CLP/GHS]

Skin Sens. 1, H317

The product is classified as hazardous according to Regulation (EC) 1272/2008 as amended.

See Section 16 for the full text of the H statements declared above.

See Section 11 for more detailed information on health effects and symptoms.

2.2 Label elements

SECTION 2: Hazards identification

Hazard pictograms



Signal word

: Warning

Hazard statements

: May cause an allergic skin reaction.

Precautionary statements

General

: P102 - Keep out of reach of children.
P103 - Read label before use.
P101 - If medical advice is needed, have product container or label at hand.

Prevention

: P261 - Avoid breathing spray.
P280 - Wear protective gloves and eye protection:
- gloves nitrile rubber Safety glasses with side shields.

Response

: P302 - IF ON SKIN:
P352 - Wash with plenty of soap and water.
P333 - If skin irritation or rash occurs:
P313 - Get medical attention.

Storage

: Not applicable.

Disposal

: P501 - Dispose of contents and container in accordance with all local, regional, national and international regulations.

Hazardous ingredients

: 1,2-benzisothiazol-3(2H)-one
2-octyl-2H-isothiazol-3-one
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and
2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)

Supplemental label elements

: Not applicable.

Annex XVII - Restrictions on the manufacture, placing on the market and use of certain dangerous substances, mixtures and articles

: Not applicable.

Special packaging requirements

Containers to be fitted with child-resistant fastenings

: Not applicable.

Tactile warning of danger

: Not applicable.

2.3 Other hazards

Other hazards which do not result in classification

: None known.

SECTION 3: Composition/information on ingredients

3.2 Mixtures

: Mixture

Product/ingredient name	Identifiers	%	Classification	
			Regulation (EC) No. 1272/2008 [CLP]	Type

SECTION 3: Composition/information on ingredients

triethoxyoctylsilane	EC: 220-941-2 CAS: 2943-75-1	≥1 - <3	Skin Irrit. 2, H315	[1]
diuron (ISO)	EC: 206-354-4 CAS: 330-54-1 Index: 006-015-00-9	<0.1	Acute Tox. 4, H302 Carc. 2, H351 STOT RE 2, H373 Aquatic Acute 1, H400 Aquatic Chronic 1, H410	[1] [2]
pyrithione zinc	EC: 236-671-3 CAS: 13463-41-7	<0.1	Acute Tox. 3, H301 Acute Tox. 3, H331 Eye Dam. 1, H318 Aquatic Acute 1, H400 Aquatic Chronic 1, H410	[1]
Reaction mass of: 5-chloro-2-methyl- 4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H- isothiazol-3-one [EC no. 220-239-6] (3:1)	EC: 611-341-5 CAS: 55965-84-9 Index: 613-167-00-5	<0.1	Acute Tox. 3, H301	[1]
			Acute Tox. 3, H311 Acute Tox. 3, H331 Skin Corr. 1B, H314 Eye Dam. 1, H318 Skin Sens. 1, H317 Aquatic Acute 1, H400 Aquatic Chronic 1, H410 See Section 16 for the full text of the H statements declared above.	

There are no additional ingredients present which, within the current knowledge of the supplier and in the concentrations applicable, are classified as hazardous to health or the environment, are PBTs, vPvBs or Substances of equivalent concern, or have been assigned a workplace exposure limit and hence require reporting in this section.

Type

[1] Substance classified with a health or environmental hazard

[2] Substance with a workplace exposure limit

[3] Substance meets the criteria for PBT according to Regulation (EC) No. 1907/2006, Annex XIII

[4] Substance meets the criteria for vPvB according to Regulation (EC) No. 1907/2006, Annex XIII

[5] Substance of equivalent concern

Occupational exposure limits, if available, are listed in Section 8.

SECTION 4: First aid measures

4.1 Description of first aid measures

- General** : In all cases of doubt, or when symptoms persist, seek medical attention. Never give anything by mouth to an unconscious person. If unconscious, place in recovery position and seek medical advice.
- Eye contact** : Remove contact lenses, irrigate copiously with clean, fresh water, holding the eyelids apart for at least 10 minutes and seek immediate medical advice.
- Inhalation** : Remove to fresh air. Keep person warm and at rest. If not breathing, if breathing is irregular or if respiratory arrest occurs, provide artificial respiration or oxygen by trained personnel.
- Skin contact** : Remove contaminated clothing and shoes. Wash skin thoroughly with soap and water or use recognised skin cleanser. Do NOT use solvents or thinners.
- Ingestion** : If swallowed, seek medical advice immediately and show the container or label. Keep person warm and at rest. Do NOT induce vomiting.
- Protection of first-aiders** : No action shall be taken involving any personal risk or without suitable training. It may be dangerous to the person providing aid to give mouth-to-mouth resuscitation. Wash contaminated clothing thoroughly with water before removing it, or wear gloves.

SECTION 4: First aid measures

4.2 Most important symptoms and effects, both acute and delayed

There are no data available on the mixture itself. The mixture has been assessed following the conventional method of the CLP Regulation (EC) No 1272/2008 and is classified for toxicological properties accordingly. See Sections 2 and 3 for details.

Exposure to component solvent vapour concentrations in excess of the stated occupational exposure limit may result in adverse health effects such as mucous membrane and respiratory system irritation and adverse effects on the kidneys, liver and central nervous system. Symptoms and signs include headache, dizziness, fatigue, muscular weakness, drowsiness and, in extreme cases, loss of consciousness.

Solvents may cause some of the above effects by absorption through the skin. Repeated or prolonged contact with the mixture may cause removal of natural fat from the skin, resulting in non-allergic contact dermatitis and absorption through the skin.

If splashed in the eyes, the liquid may cause irritation and reversible damage.

This takes into account, where known, delayed and immediate effects and also chronic effects of components from short-term and long-term exposure by oral, inhalation and dermal routes of exposure and eye contact.

Contains 1,2-benzisothiazol-3(2H)-one, 2-octyl-2H-isothiazol-3-one, Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1). May produce an allergic reaction.

4.3 Indication of any immediate medical attention and special treatment needed

Notes to physician : In case of inhalation of decomposition products in a fire, symptoms may be delayed. The exposed person may need to be kept under medical surveillance for 48 hours.

Specific treatments : No specific treatment.

See toxicological information (Section 11)

SECTION 5: Firefighting measures

5.1 Extinguishing media

Suitable extinguishing media : Recommended: alcohol-resistant foam, CO₂, powders, water spray.

Unsuitable extinguishing media : Do not use water jet.

5.2 Special hazards arising from the substance or mixture

Hazards from the substance or mixture : Fire will produce dense black smoke. Exposure to decomposition products may cause a health hazard.

Hazardous thermal decomposition products : Decomposition products may include the following materials: carbon monoxide, carbon dioxide, smoke, oxides of nitrogen.

5.3 Advice for firefighters

Special protective actions for fire-fighters : Cool closed containers exposed to fire with water. Do not release runoff from fire to drains or watercourses.

Special protective equipment for fire-fighters : Appropriate breathing apparatus may be required.

Additional information : No unusual hazard if involved in a fire.

SECTION 6: Accidental release measures

Due to the organic solvents content of the mixture:

6.1 Personal precautions, protective equipment and emergency procedures

For non-emergency personnel : Exclude sources of ignition and ventilate the area. Avoid breathing vapour or mist. Refer to protective measures listed in sections 7 and 8.

For emergency responders : If specialised clothing is required to deal with the spillage, take note of any information in Section 8 on suitable and unsuitable materials. See also the information in "For non-emergency personnel".

6.2 Environmental precautions : Avoid contact of spilt material with soil and prevent runoff entering surface waterways. See section 13 for waste disposal information.

6.3 Methods and material for containment and cleaning up

Small spill : Stop leak if without risk. Move containers from spill area. Dilute with water and mop up if water-soluble. Alternatively, or if water-insoluble, absorb with an inert dry material and place in an appropriate waste disposal container. Dispose of via a licensed waste disposal contractor.

Large spill : For small spills, add absorbent (soil may be used in the absence of other suitable materials), scoop up material and place in a sealable, liquid-proof container for disposal. For large spills, dyke spilt material or otherwise contain it to ensure runoff does not reach a waterway. Place spilt material in an appropriate container for disposal. Preferably clean with a detergent. Avoid using solvents. Do not allow to enter drains or watercourses. If the product contaminates lakes, rivers, or sewers, inform the appropriate authorities in accordance with local regulations.

6.4 Reference to other sections : See Section 1 for emergency contact information.
See Section 8 for information on appropriate personal protective equipment.
See Section 13 for additional waste treatment information.

SECTION 7: Handling and storage

The information in this section contains generic advice and guidance.

7.1 Precautions for safe handling : Keep away from heat, sparks and flame.
Avoid contact with skin and eyes. Avoid the inhalation of dust, particulates, spray or mist arising from the application of this mixture. Avoid inhalation of dust from sanding.
Eating, drinking and smoking should be prohibited in areas where this material is handled, stored and processed.
Put on appropriate personal protective equipment (see Section 8).
Never use pressure to empty. Container is not a pressure vessel.
Always keep in containers made from the same material as the original one.
Comply with the health and safety at work laws. Do not allow to enter drains or watercourses.

When operators, whether spraying or not, have to work inside the spray booth, ventilation is unlikely to be sufficient to control particulates and solvent vapour in all cases. In such circumstances they should wear a compressed air-fed respirator during the spraying process and until such time as the particulates and solvent vapour concentration has fallen below the exposure limits.

7.2 Conditions for safe storage, including any incompatibilities

SECTION 7: Handling and storage

Store in accordance with local regulations.

Notes on joint storage

Keep away from: oxidising agents, strong alkalis, strong acids.

Additional information on storage conditions

Observe label precautions. Do not store below the following temperature: 0°C (32°F). Store in a dry, cool and well-ventilated area. Keep away from heat and direct sunlight. Keep away from sources of ignition. No smoking. Prevent unauthorised access. Containers that have been opened must be carefully resealed and kept upright to prevent leakage.

7.3 Specific end use(s)

Recommendations : Not available.

Industrial sector specific solutions : Not available.

SECTION 8: Exposure controls/personal protection

The information in this section contains generic advice and guidance. Information is provided based on typical anticipated uses of the product. Additional measures might be required for bulk handling or other uses that could significantly increase worker exposure or environmental releases.

8.1 Control parameters

Occupational exposure limits

Product/ingredient name	Exposure limit values
diuron (ISO)	EH40/2005 WELs (United Kingdom (UK), 12/2011). TWA: 10 mg/m ³ 8 hours.

Recommended monitoring procedures : If this product contains ingredients with exposure limits, personal, workplace atmosphere or biological monitoring may be required to determine the effectiveness of the ventilation or other control measures and/or the necessity to use respiratory protective equipment. Reference should be made to monitoring standards, such as the following: European Standard EN 689 (Workplace atmospheres - Guidance for the assessment of exposure by inhalation to chemical agents for comparison with limit values and measurement strategy) European Standard EN 14042 (Workplace atmospheres - Guide for the application and use of procedures for the assessment of exposure to chemical and biological agents) European Standard EN 482 (Workplace atmospheres - General requirements for the performance of procedures for the measurement of chemical agents) Reference to national guidance documents for methods for the determination of hazardous substances will also be required.

DNELs/DMELs

No DNELs/DMELs available.

PNECs

No PNECs available

8.2 Exposure controls

Appropriate engineering controls : Provide adequate ventilation. Where reasonably practicable, this should be achieved by the use of local exhaust ventilation and good general extraction. If these are not sufficient to maintain concentrations of particulates and solvent vapours below the OEL, suitable respiratory protection must be worn.

Individual protection measures

Hygiene measures : Wash hands, forearms and face thoroughly after handling chemical products, before eating, smoking and using the lavatory and at the end of the working period. Appropriate techniques should be used to remove potentially contaminated clothing. Contaminated work clothing should not be allowed out of the workplace. Wash contaminated clothing before reusing. Ensure that eyewash stations and safety showers are close to the workstation location.

SECTION 8: Exposure controls/personal protection

Eye/face protection : Safety eyewear complying with an approved standard should be used when a risk assessment indicates this is necessary to avoid exposure to liquid splashes, mists, gases or dusts. If contact is possible, the following protection should be worn, unless the assessment indicates a higher degree of protection: safety glasses with side-shields. Recommended: safety glasses with side-shields (EN 166)

Skin protection

Hand protection

There is no one glove material or combination of materials that will give unlimited resistance to any individual or combination of chemicals.

The breakthrough time must be greater than the end use time of the product.

The instructions and information provided by the glove manufacturer on use, storage, maintenance and replacement must be followed.

Gloves should be replaced regularly and if there is any sign of damage to the glove material.

Always ensure that gloves are free from defects and that they are stored and used correctly.

The performance or effectiveness of the glove may be reduced by physical/chemical damage and poor maintenance.

Barrier creams may help to protect the exposed areas of the skin but should not be applied once exposure has occurred.

Gloves : For prolonged or repeated handling, use the following type of gloves:

Recommended: > 8 hours (breakthrough time): nitrile rubber (0.5mm)

The recommendation for the type or types of glove to use when handling this product is based on information from the following source:

EN 374-3 : 2003

The user must check that the final choice of type of glove selected for handling this product is the most appropriate and takes into account the particular conditions of use, as included in the user's risk assessment.

Body protection : Personal protective equipment for the body should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Recommended: Wear overalls or long sleeved shirt. (EN 467)

Other skin protection : Appropriate footwear and any additional skin protection measures should be selected based on the task being performed and the risks involved and should be approved by a specialist before handling this product.

Respiratory protection : Respirator selection must be based on known or anticipated exposure levels, the hazards of the product and the safe working limits of the selected respirator. Recommended: organic vapour (Type A) and particulate filter (EN 141).

Environmental exposure controls : Emissions from ventilation or work process equipment should be checked to ensure they comply with the requirements of environmental protection legislation. In some cases, fume scrubbers, filters or engineering modifications to the process equipment will be necessary to reduce emissions to acceptable levels.

SECTION 9: Physical and chemical properties

9.1 Information on basic physical and chemical properties

Appearance

Physical state : Liquid.

Colour : Various

Odour : Not available.

Odour threshold : Not available.

pH : 7.5

Melting point/freezing point : 0°C

Initial boiling point and boiling range : >100°C

Flash point : [Product does not sustain combustion.]

Evaporation rate : <1 (butyl acetate = 1)

SECTION 9: Physical and chemical properties

Flammability (solid, gas)	: Non-flammable in the presence of the following materials or conditions: open flames, sparks and static discharge, heat and shocks and mechanical impacts. Non-flammable but will burn on prolonged exposure to flame or high temperature.
Upper/lower flammability or explosive limits	: Not applicable.
Vapour pressure	: Not available.
Vapour density	: >1 [Air = 1]
Relative density	: 1.28
Solubility(ies)	: Soluble in the following materials: cold water and hot water. Very slightly soluble in the following materials: methanol and acetone.
Partition coefficient: n-octanol/ water	: Not available.
Auto-ignition temperature	: Not available.
Decomposition temperature	: Not available.
Viscosity	: Dynamic (room temperature): 1700 mPa·s
Explosive properties	: Not applicable.
Oxidising properties	: Not available.

9.2 Other information

No additional information.

SECTION 10: Stability and reactivity

10.1 Reactivity	: No specific test data related to reactivity available for this product or its ingredients.
10.2 Chemical stability	: Stable under recommended storage and handling conditions (see Section 7).
10.3 Possibility of hazardous reactions	: Under normal conditions of storage and use, hazardous reactions will not occur.
10.4 Conditions to avoid	: When exposed to high temperatures may produce hazardous decomposition products.
10.5 Incompatible materials	: Keep away from the following materials to prevent strong exothermic reactions: oxidising agents, strong alkalis, strong acids.
10.6 Hazardous decomposition products	: Under normal conditions of storage and use, hazardous decomposition products should not be produced. If involved in a fire, toxic gases including CO, CO ₂ and smoke can be generated.

SECTION 11: Toxicological information

11.1 Information on toxicological effects

There are no data available on the mixture itself. The mixture has been assessed following the conventional method of the CLP Regulation (EC) No 1272/2008 and is classified for toxicological properties accordingly. See Sections 2 and 3 for details.

Exposure to component solvent vapour concentrations in excess of the stated occupational exposure limit may result in adverse health effects such as mucous membrane and respiratory system irritation and adverse effects on the kidneys, liver and central nervous system. Symptoms and signs include headache, dizziness, fatigue, muscular weakness, drowsiness and, in extreme cases, loss of consciousness.

Solvents may cause some of the above effects by absorption through the skin. Repeated or prolonged contact with the mixture may cause removal of natural fat from the skin, resulting in non-allergic contact dermatitis and absorption through the skin.

If splashed in the eyes, the liquid may cause irritation and reversible damage.

SECTION 11: Toxicological information

This takes into account, where known, delayed and immediate effects and also chronic effects of components from short-term and long-term exposure by oral, inhalation and dermal routes of exposure and eye contact.

Contains 1,2-benzisothiazol-3(2H)-one, 2-octyl-2H-isothiazol-3-one, Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1). May produce an allergic reaction.

Acute toxicity

Product/ingredient name	Result	Species	Dose	Exposure
diuron (ISO)	LD50 Dermal	Rat	>5 g/kg	-
	LD50 Oral	Rat	1 g/kg	-
pyrithione zinc	LD50 Oral	Rat	4150 mg/kg	-
	LC50 Inhalation Dusts and mists	Rat	140 mg/m ³	4 hours
	LD50 Dermal	Rabbit	100 mg/kg	-
	LD50 Oral	Rat	177 mg/kg	-
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	LD50 Oral	Rat	53 mg/kg	-

Conclusion/Summary : Based on available data, the classification criteria are not met.

Acute toxicity estimates

Not available.

Irritation/Corrosion

Product/ingredient name	Result	Species	Score	Exposure	Observation
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	Skin - Severe irritant	Human	-	0.01 Percent	-

Conclusion/Summary

Skin : Based on available data, the classification criteria are not met.

Eyes : Based on available data, the classification criteria are not met.

Respiratory : Based on available data, the classification criteria are not met.

Sensitisation**Conclusion/Summary**

Skin : May cause an allergic skin reaction.

Respiratory : Based on available data, the classification criteria are not met.

Mutagenicity

Conclusion/Summary : Based on available data, the classification criteria are not met.

Carcinogenicity

Conclusion/Summary : Based on available data, the classification criteria are not met.

Reproductive toxicity

Conclusion/Summary : Based on available data, the classification criteria are not met.

Teratogenicity

Conclusion/Summary : Not available.

Specific target organ toxicity (single exposure)

Not available.

Specific target organ toxicity (repeated exposure)

SECTION 11: Toxicological information

Product/ingredient name	Category	Route of exposure	Target organs
diuron (ISO)	Category 2	Not determined	Not determined

Aspiration hazard

Not available.

Other information : Not available.**SECTION 12: Ecological information****12.1 Toxicity**

There are no data available on the mixture itself.

Do not allow to enter drains or watercourses.

The mixture has been assessed following the summation method of the CLP Regulation (EC) No 1272/2008 and is not classified as hazardous to the environment, but contains substance(s) hazardous to the environment. See section 3 for details.

Product/ingredient name	Result	Species	Exposure
diuron (ISO)	Acute EC50 2.26 µg/l Marine water	Algae - Coccolithus huxleyi - Exponential growth phase	72 hours
	Acute EC50 0.0007 mg/l Fresh water	Algae - Pseudokirchneriella subcapitata	96 hours
	Acute EC50 1000 µg/l Fresh water	Crustaceans - Ceriodaphnia dubia - Neonate	48 hours
	Acute LC50 380 µg/l Fresh water	Crustaceans - Gammarus lacustris	48 hours
	Chronic NOEC 0.54 µg/l Marine water	Algae - Coccolithus huxleyi - Exponential growth phase	72 hours
	Chronic NOEC 33.4 µg/l Fresh water	Fish - Pimephales promelas - Embryo	63 days
	pyrithione zinc	Algae - Thalassiosira pseudonana	96 hours
		Crustaceans - Ilyocypris dentifera	48 hours
		Crustaceans - Chydorus sphaericus	48 hours
		Daphnia spec. - Daphnia magna	48 hours
		Daphnia spec. - Daphnia magna - Nauplii	48 hours
		Fish - Pimephales promelas	96 hours
		Algae - Thalassiosira pseudonana	96 hours
		Algae - Selenastrum capricornutum	72 hours
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	Acute EC50 0.027 mg/l		
	Acute EC50 0.126 mg/l	Daphnia spec.	48 hours
	Acute LC50 0.28 mg/l	Fish	96 hours
	Acute LC50 0.188 mg/l	Fish	96 hours
	Acute NOEC 0.098 mg/l	Fish	96 hours

Conclusion/Summary : Based on available data, the classification criteria are not met.**12.2 Persistence and degradability**

SECTION 12: Ecological information

Product/ingredient name	Test	Result	Dose	Inoculum
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	OECD 301D	>60 % - Readily - 28 days	-	-

Conclusion/Summary : This product has not been tested for biodegradation. Based on available data, the classification criteria are not met.

Product/ingredient name	Aquatic half-life	Photolysis	Biodegradability
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	-	-	Readily

12.3 Bioaccumulative potential

Product/ingredient name	LogP _{ow}	BCF	Potential
diuron (ISO)	2,67	14,125375446	low
pyrithione zinc	0,9	-	low
Reaction mass of: 5-chloro-2-methyl-4-isothiazolin-3-one [EC no. 247-500-7] and 2-methyl-2H-isothiazol-3-one [EC no. 220-239-6] (3:1)	-0.83 to 0.75	-	low

12.4 Mobility in soil

Soil/water partition coefficient (K_{oc}) : Not available.

Mobility : Nonvolatile liquid.

12.5 Results of PBT and vPvB assessment

PBT : Not applicable.

vPvB : Not applicable.

12.6 Other adverse effects : No known significant effects or critical hazards.

SECTION 13: Disposal considerations

The information in this section contains generic advice and guidance.

13.1 Waste treatment methods**Product**

Methods of disposal : The generation of waste should be avoided or minimised wherever possible. Disposal of this product, solutions and any by-products should at all times comply with the requirements of environmental protection and waste disposal legislation and any regional local authority requirements. Dispose of surplus and non-recyclable products via a licensed waste disposal contractor. Waste should not be disposed of untreated to the sewer unless fully compliant with the requirements of all authorities with jurisdiction.

Hazardous waste : Yes.

SECTION 13: Disposal considerations

- Disposal considerations** : Do not allow to enter drains or watercourses.
Dispose of according to all federal, state and local applicable regulations.
If this product is mixed with other wastes, the original waste product code may no longer apply and the appropriate code should be assigned.
For further information, contact your local waste authority.

European waste catalogue (EWC)

The European Waste Catalogue classification of this product, when disposed of as waste, is:

Waste code	Waste designation
08 01 15*	aqueous sludges containing paint or varnish containing organic solvents or other dangerous substances

Packaging

- Methods of disposal** : The generation of waste should be avoided or minimised wherever possible. Waste packaging should be recycled. Incineration or landfill should only be considered when recycling is not feasible.
- Disposal considerations** : Using information provided in this safety data sheet, advice should be obtained from the relevant waste authority on the classification of empty containers.
Empty containers must be scrapped or reconditioned.
Not emptied containers are hazardous waste.
- Special precautions** : This material and its container must be disposed of in a safe way. Care should be taken when handling emptied containers that have not been cleaned or rinsed out. Empty containers or liners may retain some product residues. Avoid dispersal of spilt material and runoff and contact with soil, waterways, drains and sewers.

SECTION 14: Transport information

	ADR/RID	ADN	IMDG	IATA
14.1 UN number	Not regulated.	Not regulated.	Not regulated.	Not regulated.
14.2 UN proper shipping name	-	-	-	-
14.3 Transport hazard class(es)	-	-	-	-
14.4 Packing group	-	-	-	-
14.5 Environmental hazards	No.	No.	No.	No.
Additional information	-	-	-	-

- 14.6 Special precautions for user** : **Transport within user's premises:** always transport in closed containers that are upright and secure. Ensure that persons transporting the product know what to do in the event of an accident or spillage.

SECTION 15: Regulatory information

15.1 Safety, health and environmental regulations/legislation specific for the substance or mixture

EU Regulation (EC) No. 1907/2006 (REACH)

Annex XIV - List of substances subject to authorisation

Annex XIV

None of the components are listed.

Substances of very high concern

None of the components are listed.

Annex XVII - Restrictions : Not applicable.
**on the manufacture,
 placing on the market
 and use of certain
 dangerous substances,
 mixtures and articles**

Other EU regulations

VOC for Ready-for-Use Mixture : IIA/d. Interior/exterior trim and cladding paints for wood and metal. EU limit value for this product : 130g/l (2010.)
 This product contains a maximum of 35 g/l VOC.

Europe inventory : All components are listed or exempted.

Product/ingredient name	Carcinogenic effects	Mutagenic effects	Developmental effects	Fertility effects
diuron (ISO)	Carc. 2, H351	-	-	-

Seveso Directive

This product is not controlled under the Seveso Directive.

References : EH40/2005 Workplace exposure limits
 Conforms to Regulation (EC) No. 1907/2006 (REACH), Annex II, as amended by Regulation (EU) No. 2015/830

International regulations

Chemical Weapon Convention List Schedules I, II & III Chemicals

Not listed.

Montreal Protocol (Annexes A, B, C, E)

Not listed.

Stockholm Convention on Persistent Organic Pollutants

Not listed.

Rotterdam Convention on Prior Inform Consent (PIC)

Not listed.

UNECE Aarhus Protocol on POPs and Heavy Metals

Not listed.

CN code : 3209 90 00

International lists

National inventory

Australia : Not determined.
Canada : Not determined.
China : Not determined.
Japan : Not determined.
Malaysia : Not determined.
New Zealand : Not determined.
Philippines : Not determined.

SECTION 15: Regulatory information

Republic of Korea : Not determined.
Taiwan : Not determined.
United States : Not determined.

15.2 Chemical Safety Assessment : No Chemical Safety Assessment has been carried out.

SECTION 16: Other information

 Indicates information that has changed from previously issued version.

Abbreviations and acronyms : ATE = Acute Toxicity Estimate
 CLP = Classification, Labelling and Packaging Regulation [Regulation (EC) No. 1272/2008]
 DMEL = Derived Minimal Effect Level
 DNEL = Derived No Effect Level
 EUH statement = CLP-specific Hazard statement
 PBT = Persistent, Bioaccumulative and Toxic
 PNEC = Predicted No Effect Concentration
 RRN = REACH Registration Number
 vPvB = Very Persistent and Very Bioaccumulative

Procedure used to derive the classification according to Regulation (EC) No. 1272/2008 [CLP/GHS]

Classification	Justification
Skin Sens. 1, H317	Calculation method

Full text of H-phrases referred to in sections 2 and 3

Full text of abbreviated H statements :	H301 H302 H311 H314 H315 H317 H318 H331 H351 H373 H400 H410	Toxic if swallowed. Harmful if swallowed. Toxic in contact with skin. Causes severe skin burns and eye damage. Causes skin irritation. May cause an allergic skin reaction. Causes serious eye damage. Toxic if inhaled. Suspected of causing cancer. May cause damage to organs through prolonged or repeated exposure. Very toxic to aquatic life. Very toxic to aquatic life with long lasting effects.
--	--	---

Full text of classifications [CLP/GHS] :	Acute Tox. 3, H301 Acute Tox. 3, H311 Acute Tox. 3, H331 Acute Tox. 4, H302 Aquatic Acute 1, H400 Aquatic Chronic 1, H410 Carc. 2, H351 Eye Dam. 1, H318 Skin Corr. 1B, H314 Skin Irrit. 2, H315 Skin Sens. 1, H317 STOT RE 2, H373	ACUTE TOXICITY (oral) - Category 3 ACUTE TOXICITY (dermal) - Category 3 ACUTE TOXICITY (inhalation) - Category 3 ACUTE TOXICITY (oral) - Category 4 ACUTE AQUATIC HAZARD - Category 1 LONG-TERM AQUATIC HAZARD - Category 1 CARCINOGENICITY - Category 2 SERIOUS EYE DAMAGE/ EYE IRRITATION - Category 1 SKIN CORROSION/IRRITATION - Category 1B SKIN CORROSION/IRRITATION - Category 2 SKIN SENSITIZATION - Category 1 SPECIFIC TARGET ORGAN TOXICITY (REPEATED EXPOSURE) - Category 2
---	--	--

Date of printing : 31/10/2016
Date of issue/ Date of revision : 31/10/2016
Date of previous issue : No previous validation

SECTION 16: Other information

Version : 1

Notice to reader

The information in this Safety Data Sheet is based on the present state of knowledge and current legislation. It provides guidance on health, safety and environmental aspects of the product and should not be construed as any guarantee of technical performance or suitability for particular applications. The product should not be used for purposes other than those shown in Section 1 without first referring to the supplier and obtaining written handling instructions. As the specific conditions of use of the product are outside the supplier's control, the user is responsible for ensuring that the requirements of relevant legislation are complied with. The information contained in this safety data sheet does not constitute the user's own assessment of workplace risks, as required by other health and safety legislation.