



























Key	
<span style="display:inline-block; width:15px; height:10px; background-color:#c8e6c9;"></span>	SAMPLE ON SITE
<span style="display:inline-block; width:15px; height:10px; background-color:#ffe0b2;"></span>	HIGH-RES IMAGE INCLUDED, SAMPLE AVAILABLE ON SITE UPON REQUEST
<span style="display:inline-block; width:15px; height:10px; background-color:#bdbdbd;"></span>	NOT REQUIRED/ N/A

REF	Description	Proposed Specification	Manufacturer Details	Sample	Comments	Photograph
<b>ROOF COVERINGS</b>						
RF01	Lead	H71/110 & H71/116			New to match existing	n/a
RF02	Slate	H62/105			Reclaimed to match existing	n/a
RF03	Single Ply Membrane	J42/110-112 Single Ply Roof Membrane in Lead Grey colour	Sika Limited Watchmead Welwyn Garden City AL7 1BQ 01707 394 444			
RF06A	Standing seam Zinc roof and Gutters (North Annexe)	H74/110A - Anthra-Zinc by VMZINC	VMZINC Collier House Mead Lane Hertford Herts SG13 7AX Tel: 0203 445 5640			 
RF06B	Batten Roll Zinc roof (Guildhall)	H74/111 - Natural Zinc by MZINC	VMZINC Collier House Mead Lane Hertford Herts SG13 7AX Tel: 0203 445 5640			 
RF07	New Clay Tiles to Roof V7	Brown 'Rosemary' Clay tile	N/A		New Clay Tiles to best match existing. Informal approval of chosen tile by CYC via email 16.06.2021, following receipt of photograph.	
<b>EXTERNAL WALLS</b>						
EXW1A	Petersen Brick D46 FF - 228x108x40mm bricks	F10/110	Petersen TEGL A/S, Nybolnørvej 14, DK-6310, Broager, Denmark, +457444 1236, info@petersen-tegl.dk		Sample panel signed off on site by CYC 12.03.2020. Submitted for formal Discharge of Conditions 10.08.2020	

REF	Description	Proposed Specification	Manufacturer Details	Sample	Comments	Photograph
EXW2	London Stock Brick	F10/110 - imperial size yellow brick	Imperial Handmade Bricks, Grindle House Farm, Grindle Road, Grindle Near Shifnal, Shropshire, TF11 9JR, 01952 750816, sales@imperialbricks.co.uk www.imperialbricks.co.uk		Material signed off by CYC via email 29.01.2020, following receipt of BFF's brickwork report.	
EXW3	Existing red brick salvaged from site	Red Bricks salvaged from elsewhere on site and used on East elevation of the muniment room, facing Vodka Revolution	N/A - Existing			
EXW4	Zinc Standing Seam Cladding to Small section of South Range	Anthra-Zinc by VMZINC	VMZINC Collier House Mead Lane Hertford Herts SG13 7AX Tel: 0203 445 5640			 
EXW5	Reclaimed Suffolk White Bricks	Reclaimed Bricks for use on Vent upstands (to existing coal chutes) in Victorian Block Corridor	Reclaimed Brick Company, Clifton Works, Hillfoot Road, Sheffield, S3 8AA			
WINDOWS, GLAZING & DOORS						
N/A	Curtain Walling	Aluminium/ Steel Frame, Matte finish, Anthracite RAL 7016	Schueco UK Limited Whitehall Avenue, Kingston, Milton Keynes, MK10 0AL / Senior Architectural Systems Eland Rd, Denaby Main, Doncaster DN12 4HA			
N/A	Windows	Aluminium/ Steel Frame, Matt finish, Anthracite RAL 7016	Schueco UK Limited Whitehall Avenue, Kingston, Milton Keynes, MK10 0AL / Senior Architectural Systems Eland Rd, Denaby Main, Doncaster DN12 4HA			
N/A	Doors	Aluminium/ Steel Frame, Matt finish, Anthracite RAL 7016	Schueco UK Limited Whitehall Avenue, Kingston, Milton Keynes, MK10 0AL / Senior Architectural Systems Eland Rd, Denaby Main, Doncaster DN12 4HA			

REF	Description	Proposed Specification	Manufacturer Details	Sample	Comments	Photograph
N/A	Rooflights	Aluminium Frame Trim, Matt finish, Anthracite RAL 7016	The Rooflight Company Wychwood Business Centre, Milton Rd, Shipton-under-Wychwood, Chipping Norton OX7 6XU			
MISC						
N/A	North Annexe Downpipes	PPC Aluminium, in Anthracite (RAL 7016) to match windows/doors	N/A			
N/A	Louvres: - North Annexe Chimneys - South Range Louvre - Louvres to vent upstands (existing coal chutes)	PPC Aluminium, in Anthracite (RAL 7016) to match windows/doors	N/A			
N/A	Metal Balustrading: - Riverside Balustrade - Guarding to Graduate Beer Garden	PPC metal in Anthracite (RAL 7016) to match windows/doors	N/A			
N/A	Stair 08 Balustrade: - Zinc Standing Seam to outside of balustrade - Timber cladding to inside of balustrade	Anthra-Zinc by VMZINC to outside / Oak cladding with Osmo UVIWAX UV-Protection, 7266 White Spruce (transparent) to inside to match timber soffits;	VMZINC Collier House Mead Lane Hertford Herts SG13 7AX Tel: 0203 445 5640			
N/A	Timber soffits: - North Annexe Ground floor and 1st floor external passageways - Soffit above restaurant terrace - Feature window terrace soffit	Oak soffit cladding with Osmo UVIWAX UV-Protection, 7266 White Spruce (transparent)	N/A			
N/A	Bin Store Cladding, Common Hall Yard	Oak cladding with Osmo UVIWAX UV-Protection, 7266 White Spruce (transparent)	N/A			
HARD LANDSCAPING/ GROUND COVER						

REF	Description	Proposed Specification	Manufacturer Details	Sample	Comments	Photograph
N/A	Paving: Riverside Garden and Alleyway	Marshalls Conservation X Paving Cream Textured as Q25/315 on sub-base as engineers specification. Mortar as Q25/440 and Grout as Q25/455.	Marshalls; Landscape House, Premier Way, Lowfields Business Park, Elland HX5 9HT			
N/A	Tactile Paving: Riverside Garden	Marshalls Hazard Warning tactile slab to provide route for visually impaired (to top and bottom of step flights) as Q25/321 on sub-base as engineers specification. Mortar as Q25/440 and Grout as Q25/455.	Marshalls; Landscape House, Premier Way, Lowfields Business Park, Elland HX5 9HT			
N/A	Paving: Riverside Garden around Tree	Setts (150x150x50mm) in Pepper as Q25/330 on sub-base as engineers specification. Mortar as Q25/440 and Grout as Q25/455.	AG (Achenson & Glover) 4 Marlin Office Village 1250 Chester Road, Castle Vale Birmingham, B35 7AZ			
N/A	Oak Sleepers	To new Bench top in Common Hall Yard	N/A			
N/A	Paving: Common Hall Yard (vehicular and pedestrian access)	New Yorkstone paving as Q25/311 on sub-base as engineers specification. Mortar as Q25/440 and Grout as Q25/455. Suitable for light vehicular traffic in Common Hall Yard.	Marshalls; Landscape House, Premier Way, Lowfields Business Park, Elland HX5 9HT			
N/A	Paving: Common Hall Yard	Existing Yorkstone Slabs retained and reinstated	N/A Existing slabs			
N/A	Steps: Common Hall Yard	New Yorkstone Blocks forming new steps, 1000mm lengths. Flamed finish to match new adjacent Common Hall Yard Paving.	N/A - Contractor's supplier			