


Location Plan
Scale 1 : 50000

The junction that the proposed vehicular access forms with the public road to be kerbed to radii of 5.0m, the minimum width at the throat of the bell mouth so formed to be 5.5m. The area within the bell mouth & for a minimum distance of 10.0m from the public road carriageway, to be constructed in accordance with the Council's Specification appropriate to the type of traffic which will use the access, & shall be surfaced with dense bitumen macadam or asphalt. First 10m to be tar with a max gradient of 1:20



Electrical:
New electrical installations to be fitted where shown, and to be designed, constructed, installed and tested in accordance with current IEE standards and BS7671: 2008.

Rev	Purpose of issue	By	Date
A	Drainage installation	PST	June 21

Description	
Sites adjacent Bridgend Ballogie Aberdeenshire AB34 5DS	
Drainage installation	
Site plan	
Date : June 2021	Drawing No.
Scale : 1:250 @ A1	2019-079/BWA
Drawn : PST	

Gerry Robb
architectural design services

Bridgend
Bridgeview Road
Aboyne
Aberdeenshire
AB34 5HB
(013398) 86359
info@gerryrobb.co.uk