

General Tree Assessment (Summary)

<i>Tree Ref</i>	<i>Species</i>	<i>H (m)</i>	<i>Spr (m)</i>	<i>Maturity</i>	<i>Condition</i>	<i>Action Recommendations</i>	<i>Costs</i>	<i>Priority</i>	<i>Done</i>	<i>Inspected</i>
Chelsfield Lane site - car park area										
0861	Ash	16	7	SM	Poor	Fell :: Fell to ground level	£250.00	1 Month	No	01-Sep-21
<p>Comment: Group of 2 no. trees to east of car park area (ownership unclear). Tagged, standing stem recently-dead. Northern stem partially-uprooted and propped in adjacent trees, overhanging Chelsfield Lane. Fell to 1 metre stumps and stack arisings neatly within woodland.</p>										
0846	Sweet Chestnut	15	4	M	Poor	Coppice :: To 0.5m stumps	£250.00	3 Months	No	01-Sep-21
<p>Comment: Tree adjacent to Chelsfield Lane. Severe decay in main fork union.</p>										
0851	Common Oak	16	10	OM	Fair	Reduce crown(s) :: See comment Remove :: Major dead wood	£795.00 £210.00	3 Months 3 Months	No No	01-Sep-21
<p>Comment: Veteran tree of high ecological value. Some internal decay indicated between buttress roots; decay fungal fruiting body (Ganoderma spp.) on 1 no. southern buttress root, with associated decay appearing to localised. Woodpecker holes in 2 no. major limbs indicating internal cavities/decay. Major dead wood in crown, overhanging car park area. Reduce height by 3 metres and lateral spread radius by approximately 4-5 metres on all sides, retaining current form as far as possible. Recommend establishing a cordon at least 2 metres around stem base to protect inner rootplate and lower stem from vehicle activity.</p>										
Age Classification:	NP Newly planted	EM Early Mature	Condition: Overall unless specified as -			C Crown				
	Y Young	M Mature				S Stem				
	SM Semi-mature	OM Over Mature				B Basal area				

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Costs	Priority	Done	Inspected
0855	Sweet chestnut	15	7	M	Fair	Remove :: Major dead wood	£30.00	3 Months	No	01-Sep-21
<p>Comment: 2 no. coppice trees immediately adjacent to Chelsfield Lane, each with 1 no. dead stem overhanging lane. Southern tree tagged.</p>										
0860	Sweet chestnut	16	7	OM	Poor	Coppice :: Recoppice	£475.00	3 Months	No	01-Sep-21
<p>Comment: 2 no. large, mature coppice stools (approximately 15 stems in total) immediately to north of car park entrance and adjacent to Chelsfield Lane. Several stems dead, with decay and poor vitality in remaining stems - recoppice all.</p>										
0864	Sweet Chestnut	14	4	Dead	Poor	Fell :: Fell to ground level	£125.00	3 Months	No	01-Sep-21
<p>Comment: Dead tree adjacent to woodland gate.</p>										
0865	Sweet chestnut	16	6	M	Fair	Remove :: Major dead wood	£75.00	3 Months	No	01-Sep-21
<p>Comment: Group of 2 no. coppice trees (smaller, western tree tagged) with major dead wood in crowns, overhanging car park area.</p>										
0868	Sweet Chestnut	16	5	M	Poor	Coppice :: Recoppice	£210.00	3 Months	No	01-Sep-21
<p>Comment: 2 no. dead stems, with severe dieback in third stem.</p>										
0869	Sweet Chestnut	15	2	SM	Poor	Fell :: Fell to ground level	£75.00	3 Months	No	01-Sep-21
<p>Comment: Severe decay in stem base.</p>										
0870	Sweet Chestnut	10	1	Dead	Poor	Fell :: Fell to ground level	£40.00	3 Months	No	01-Sep-21
<p>Comment: Dead tree.</p>										
0871	Sweet Chestnut	15	4	SM	Fair	Remove :: Faulted stems	£75.00	3 Months	No	01-Sep-21
<p>Comment: 1 no. dead, eastern stem.</p>										
<p>Age Classification: NP Newly planted EM Early Mature Condition: Overall unless specified as - C Crown Y Young M Mature S Stem SM Semi-mature OM Over Mature B Basal area</p>										

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Costs	Priority	Done	Inspected
0872	Sweet Chestnut	15	6	SM	Fair	Remove :: Faulted stems	£120.00	3 Months	No	01-Sep-21
Comment: 1 no. dead, western stem adjacent to car park perimeter fence (dead stem tagged).										
0873	Sweet Chestnut	15	6	SM	Fair	Remove :: Faulted stems	£50.00	3 Months	No	01-Sep-21
Comment: 1 no. dead, southern stem.										
0876	Sweet Chestnut	5	5	Dead	Poor	Fell :: Fell to ground level	£125.00	3 Months	No	01-Sep-21
Comment: Dead tree within car park area.										
0877	Sweet Chestnut	15	5	Dead	Poor	Fell :: Fell to ground level	£125.00	3 Months	No	01-Sep-21
Comment: 2 no. dead trees within car park area, supporting table and roof (these will need to be removed by client prior to tree works commencing). Northern tree in group tagged.										
0847	Sweet Chestnut	15	5	SM	Poor	Coppice :: To 0.5m stumps	£75.00	6 Months	No	01-Sep-21
Comment: Coppice tree with decayed stool.										
0848	Sweet Chestnut	16	5	OM	Poor	Coppice :: To 0.5m stumps	£220.00	6 Months	No	01-Sep-21
Comment: Overmature regrowth on decayed coppice stool Southern stem leaning over Chelsfield Lane.										
0852	Sweet Chestnut	15	1	Dead	Poor	Fell :: Fell to ground level	£75.00	6 Months	No	01-Sep-21
Comment: Dead, decayed tree to west of car park area (outside boundary fence) but within falling distance of car park.										
0853	Sweet Chestnut	15	1	Dead	Poor	Fell :: Fell to ground level	£75.00	6 Months	No	01-Sep-21
Comment: Dead, decayed tree to west of car park area (outside boundary fence) but within falling distance of car park.										
Age Classification: NP Newly planted EM Early Mature Condition: Overall unless specified as - C Crown Y Young M Mature S Stem SM Semi-mature OM Over Mature B Basal area										

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Costs	Priority	Done	Inspected
0858	Sweet Chestnut	15	2	SM	Poor	Fell :: Fell to ground level	£75.00	6 Months	No	01-Sep-21
Comment: Decay in stem base. NB Adjacent benches will need to be moved prior to felling works.										
0862	Sweet Chestnut	16	3	Dead	Poor	Fell :: Fell to ground level	£75.00	6 Months	No	01-Sep-21
Comment: Dead tree close to northern car park perimeter.										
0863	Sweet Chestnut	15	4	SM	Poor	Fell :: Fell to ground level	£175.00	6 Months	No	01-Sep-21
Comment: Partially-uprooted tree leaning north, towards perimeter fence.										
0866	Sweet chestnut	15	7	M	Poor	Coppice :: Recoppice	£150.00	6 Months	No	01-Sep-21
Comment: 2 no. coppice trees with poor vitality and dieback in upper crowns.										
0867	Sweet Chestnut	16	5	M	Poor	Coppice :: Recoppice	£250.00	6 Months	No	01-Sep-21
Comment: Northern stem recently-dead, with crown dieback apparent in other stems - recoppice all. Stem base obscured by stacked barrels, which will need to be moved by client prior to coppicing works.										
0875	Sweet Chestnut	15	5	M	Poor	Coppice :: Recoppice	£150.00	6 Months	No	01-Sep-21
Comment: Mature regrowth on decayed coppice stool, with cavity at base. South-western and south-eastern stems dead. Coppice all stems back to stool.										
0856	Sweet chestnut	14	10	OM	Poor	Coppice :: To 0.5m stumps	£420.00	1 year	No	01-Sep-21
Comment: 4 no. overmature coppice trees with decayed stools adjacent to/overhanging Chelsfield Lane.										
0857	Sweet Chestnut	16	7	M	Fair	Reduce faulted limbs/stems :: See comment	£275.00	1 year	No	01-Sep-21
Comment: Weak, compression union between 2 no. western stems, from 0-1.5 metres, with 1 no. stem leaning heavily to south, over static truck and yard area. Reduce leaning stem by 6 metres.										
Age Classification: NP Newly planted EM Early Mature Condition: Overall unless specified as - C Crown Y Young M Mature S Stem SM Semi-mature OM Over Mature B Basal area										

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Costs	Priority	Done	Inspected
0859	Sweet Chestnut	15	2	SM	Poor	Fell :: Fell to ground level	£75.00	1 year	No	01-Sep-21
Comment: Early decay in northern side of stem base.										
0881	Sweet Chestnut	15	2	SM	Poor	Fell :: Fell to ground level	£75.00	1 year	No	01-Sep-21
Comment: Loose, missing bark and decayed internal wood in main stem, from 0.5-1.5 metres.										
0874	Sweet Chestnut	15	5	M	Fair	Pollard :: Pollard to 5 m	£375.00	2 Years	No	01-Sep-21
Comment: Heavy lean/weighting south, over containers and yard area. Weak fork unions at base.										

Age Classification:	NP Newly planted	EM Early Mature	Condition:	Overall unless specified as -	C Crown
	Y Young	M Mature			S Stem
	SM Semi-mature	OM Over Mature			B Basal area