



Hydroclear eco sewage treatment plant. 97% pollutant cleaning.

Specification

<b>HydroClear Model:</b>	HC12
<b>Population Served:</b>	7 to 12
<b>Max. Hydraulic Load (litres /day):</b>	2400
<b>Organic Load (g BODs/day):</b>	720
<b>NH3 (g/day):</b>	96
<b>Total Capacity (litres):</b>	5950
<b>Length (mm):</b>	4500
<b>Width (mm):</b>	1400
<b>Height to Ground Level (mm):</b>	2450
<b>Empty Plant Weight (kg):</b>	550
<b>Energy Usage (kWh/day):</b>	2.5
<b>Desludging Interval (months):</b>	9
<b>Compliant with EN-12566 part 3:</b>	Yes
<b>Inlet Depth (mm):</b>	1100
<b>Outlet Depth (mm):</b>	1150
<b>Installation Depth (mm):</b>	2450



Polybed eco drainage field. 75 metres.