

Passing Bay Construction Detail



Typical passing bay construction
Construct passing bay with a minimum overall depth of 450mm comprising of a minimum of 250mm sub base material, 100mm of bituminous macadam base course material, 60mm bituminous macadam binder course and 40mm bituminous wearing course