



# LUDLOW PLUS


Ideal for refurbishment applications, where its smaller format reduces wastage.




## COLOUR AVAILABILITY




Greystone (G)




Smooth Grey (S)




Antique Brown (G)



Smooth Brown (S)



Dark Red (G)



Old English Dark Red (S)

**Key**  
(G) Granular finish  
(S) Smooth finish

## TECHNICAL DATA

Size of tile	387mm x 229mm	
Minimum pitch*	25° Smooth (75mm headlap) 22.5° Smooth (100mm headlap)	30° Granular (75mm headlap)
Maximum pitch	90°	
Minimum headlap	75mm	
Maximum gauge	312mm	
Body thickness	25mm (nominal)	
Profile depth	d > 11mm	
Cover width	204mm (nominal)	
Hanging length	361mm (nominal)	
Covering capacity (net)	15.7 tiles/m <sup>2</sup> at 75mm headlap	17.1 tiles/m <sup>2</sup> at 100mm headlap
Weight of tiling (approx.)	47kg/m <sup>2</sup> (0.46 kN/m <sup>2</sup> ) at 75mm headlap	51kg/m <sup>2</sup> (0.50 kN/m <sup>2</sup> ) at 100mm headlap
Battens required (net)	3.2 lin.m/m <sup>2</sup> at 75mm headlap	3.5 lin.m/m <sup>2</sup> at 100mm headlap
Batten size recommended	38mm x 25mm for rafters/supports not exceeding 450mm centres (fixed to BS 5534) 50mm x 25mm for rafters/supports not exceeding 600mm centres (fixed to BS 5534)	
Tile nails	50mm x 3.35mm	
Fixing clips	Eaves, verge and tile clips	
Authority	BS EN 490	

\* The minimum recommended pitch and lap may be influenced by special circumstances, please contact the Technical Advisory Service.

## SUSTAINABILITY

- ✓ A<sup>+</sup> rated in the BRE Green Guide (based on generic rating for UK produced clay interlocking tiles  
Element Refs: 812410007, 812410018, 812410049)
- ✓ BES 6001 Responsible Sourcing certified