



LEGEND

- **Scope of works**
- **Soft Landscape**
- **Native tree planting**
These will be made up of: Prunus padus, Sorbus aria, Tilia cordata. All to be 14-16 girth, container grown planted with 2x stakes.
- **Native tree planting**
Betula pendula 14-16 girth, container grown multi steam; planted with 2x stakes.
- Trees to be retained**
- Proposed Flowering Lawn**
Proposed flowering lawn mixture EL1 by Emorsgate is a complete mix composed of 20% native wild flowers and 80% slow growing grasses (by weight). To be sown in line with suppliers guidelines.
- Wildflower areas**
Pollinator seed mix PMTurf by Pictorial meadows or similar approved. Grass beds to accommodate drifts of perennial flowers. Areas to be 70% grass mix and 30% perennial flowers. To be planted in 150mm of prepared top soil over 300mm prepared sub soil.
- Native Hedgerow Shrub Planting:**
Native Hedging would be made up of the following: Blackthorn (Prunus spinosa) 25%, Hawthorn (Crataegus monogyna) 25%, Dog Rose (Rosa canina) 10%, Elder (Sambucus nigra) 10%, Alder (Alnus glutinosa) 10%, Sea Buckthorn (Hippophae rhamnoides) 10% and Wild Privet (Ligustrum vulgare) 10%. Planted in groups of 3/5/7 of each SPP plant at 0.75 M spacings
- Ornamental Pollinator Shrub Planting:**
planted 5lt pots at 4 m2 :
Lavandula angustiflora
Viburnum tinus eye price
Pholmis amazone
Pholmis russeliana
Hedera colchia
- Existing Shrub planting to be retained**
- Hedges**
Planted in groups of 3/5/7 of each SPP plant at 0.75 M spacings

Notes:
• Drawings to be read in conjunction with Access Report.

Ornamental Pollinator Shrub Planting Schedule						
Type	Pot Size	Height/Spread	Habit	Min. breaks in lower 1/3rd	Planting Density	Total No.
Hedera colchia	SLT	30-40	Bushy	4	5	42
Lavandula angustifolia	SLT	40-50	Bushy	7	4	141
Pholmis amazone	SLT	10/15	Ground Cover	-	5	149
Pholmis russeliana	SLT	15-30	Bushy	-	5	47
Viburnum tinus eye price	SLT	30-40	Bushy	4	5	182

Tree Schedule							
Species	Age/ Condition or Number of Times Transplanted	Overall Height	Girth	Clear Stem (C/S) Feathered (F)	Rootball Diameter	Notes	Total No.
Betula pendula	2x	2 metre	multi steam	2.0m	500-600mm	Container	10
Prunus padus	2x	400-450cm	14-16cm	1.8m	500-600mm	Container	8
Sorbus aria	2x	400-450cm	14-16cm	1.8m	700mm	Container	5
Tilia cordata	2x	400-450cm	14-16cm	2.0m	1000mm	Container	3

Soft Landscape Plan
1:200

PL	P01	14/09/21	Issued for Planning	REVISED BY	AP
STATUS	REV	DATE	DESCRIPTION	CHECKED BY	DH
CLIENT				ORIGINATOR NO	154345
RCHT/KIER					

CONSULTANT
STRIDE TREGLOWN
www.stride-treglow.com © Stride Treglow Limited 2019
PROJECT
RCHT West Cornwall Hospitals
St Clare Street
Penzance
TR18 2PF

DRAWING TITLE
Soft Landscape Plan

SUITABILITY STATUS	SCALE
PL : PLANNING	1 : 200 @ A1

PROJECT ORIGINATOR ZONE LEVEL TYPE ROLE CLASS NUMBER	REVISION
154345-STL-XX-ZZ-DR-L-XXXX-91040	P01