

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
6	Malus 'Jon's Orange Pippin'		150-200cm	Half Standard			BR	rr	rr	rr		
6	Malus 'Discovery'		150-200cm				BR	rr	rr	rr		
12												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
4	Malus domestica 'Sunset'			Half Standard						rr		

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
4	Malus domestica 'Sunset'			Half Standard						rr		

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
262	Calluna vulgaris		30-40cm				C	2.5L	m2		3.00	0.600
161	Cytisus scoparius		40-60cm				7	C	2L	m2	3.00	0.600
201	Erica cinerea 'Alba Minor'		30-40cm				C	2L	m2		3.00	0.600
161	Ulex europaeus		30-40cm				5	C	3L	m2	3.00	0.600
805												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
304	Cornus sanguinea	1+2	60-80cm				3	B	m		5.00	0.200
609	Corylus avellana	1+2	60-80cm				3	B	m		5.00	0.200
1217	Crataegus monogyna	1+1	80-100cm	Transplant (seed-raised)				B	m		5.00	0.200
304	Ligustrum vulgare	1+1	60-80cm				3	B	m		5.00	0.200
304	Prunus spinosa	1+1	80-100cm				3	B	m		5.00	0.200
304	Viburnum lantana	1+2	80-100cm				3	B	m		5.00	0.200
3942												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
303	Aucuba japonica 'Rozannie'		30-40cm				3	C	3L	m2	5.00	0.450
101	Berberis thunbergii 'Atropurpurea Nana'		15-20cm	Bush			4	C	3L	m2	5.00	0.450
222	Brachyglottis 'Sunshine'		30-40cm				3	C	3L	m2	5.00	0.450
188	Ceanothus 'Blue Mound'		30-40cm (D)	Bushy			5	C	3L	m2	5.00	0.450
213	Choisya 'Aztec Pearl'		30-40cm	Bushy			5	C	3L	m2	5.00	0.450
273	Cistus pulverulentus 'Sunset'		30-40cm				C	3L	m2		5.00	0.450
179	Elaeagnus x ebbingei 'Limeight'		40-60cm	Bush			3	C	3L	m2	4.00	0.500
150	Escallonia 'Apple Blossom'		40-60cm	Bush			3	C	3L	m2	4.00	0.500
143	Escallonia 'Red Elf'		40-60cm	Bushy			4	C	3L	m2	4.00	0.500
112	Eucynymus fortunei 'Blondy'	2x	20-30cm (D)	Bushy			6	C	3L	m2	5.00	0.450
296	Eucynymus fortunei 'Doris Banket'		30-40cm (D)				5	C	3L	m2	5.00	0.450
151	Oristina littoralis 'Variegata'		30-40cm				3	C	3L	m2	5.00	0.450
293	Hebe 'Mette'	2x	30-40cm	Bushy			4	C	3L	m2	5.00	0.450
345	Hebe 'Pascal'	1+1 or 1/1	30-40cm	Bush			3	C	3L	m2	5.00	0.450
199	Hypericum 'Hidcote'		20-30cm (D)	Bushy			5	C	3L	m2	5.00	0.450
327	Ilex crenata 'Convexa'	2x	20-30cm (D)	Bush			3	C	3L	m2	5.00	0.450
343	Lavandula intermedia 'Grosso'	2x	15-20cm (D)	Bushy			5	C	3L	m2	5.00	0.450
242	Lonicera nitida 'Lemon Beauty'		30-40cm	Bushy			5	C	3L	m2	5.00	0.450
202	Mahonia aquifolium 'Apollo'		20-30cm	Bush			3	C	3L	m2	5.00	0.450
202	Osmanthus burkwoodii		30-40cm				4	C	3L	m2	4.00	0.500
199	Philadelphus 'Manteau d'Hermine'		30-40cm				3	C	3L	m2	5.00	0.450
158	Phlox fruticosa		30-40cm	Bush			4	C	3L	m2	4.00	0.500
160	Phlox x fraseri 'Red Robin'	2x	30-40cm				3	C	3L	m2	4.00	0.500
215	Prunus laurocerasus 'Zabelliana'		20-30cm (D)				3	C	3L	m2	4.00	0.500
272	Santolina chamaecyparissus		20-30cm				7	C	3L	m2	5.00	0.450
155	Skimmia confusa 'Kew Green'		30-40cm (D)	Bushy			3	C	3L	m2	5.00	0.450
164	Spiraea japonica 'Goldflame'		30-40cm	Bushy			6	C	3L	m2	4.00	0.500
321	Viburnum davidii		25-30cm (D)				3	C	3L	m2	5.00	0.450
206	Viburnum opulus 'Compactum'	1+1	30-40cm	Bush			4	C	3L	m2	5.00	0.450
117	Weigela florida 'Variegata'		30-40cm	Bush			5	C	3L	m2	5.00	0.450
6559												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
2	Hedera helix 'Hibernica'		80-100cm				5	C	5L	rr		
11	Hydrangea arborescens 'petalis'		80-80cm				3	C	5L	rr		

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
2034	Carpinus betulus (Hedge)	1+1	80-100cm	Bushy			B	m			5.00	0.200
3018	Prunus laurocerasus 'Elna' (Hedge)		40-60cm	Bushy			5	C	5L	m	5.00	0.200
5842												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
80	Rosa 'Iceberg'	1+0	30-40cm	Bushy			3	B	m2		5.00	0.450
80												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
22	Aucuba japonica 'Rozannie'		30-40cm				3	C	3L	m2	5.00	0.450
22	Brachyglottis 'Sunshine'		30-40cm				3	C	3L	m2	5.00	0.450
18	Lonicera nitida 'Magister'		30-40cm				6	C	3L	m2	4.00	0.500
22	Lonicera pileata		30-40cm	Bushy			5	C	3L	m2	5.00	0.450
18	Prunus laurocerasus 'Otto Luyken'		30-40cm				3	C	3L	m2	4.00	0.500
102												

Qty	Name	Age	Height	Form	Girth	CrDm	Bks	Root	Ctr	Measure Unit	Density (no/20ln m)	Centres
2	Acer campestre		425-600cm	Standard (extra-heavy)	14-16cm		RR	rr	rr	rr		
16	Acer campestre	2x	300-350cm	Standard (Selected)	10-12cm	Min 200cm	4	RR	rr	rr		
8	Acer campestre 'Queen Elizabeth'	2x	425-600cm	Extra-heavy Standard	14-16cm	Min 200cm	7	RR	rr	rr		
5	Alnus glutinosa	2x	300-350cm	Standard	10-12cm	Min 200cm	4	RR	rr	rr		
9	Amanchier arborea 'Rubin Hill'	2x	300-350cm	Selected Standard	10-12cm	Min 200cm	5	B	rr	rr		
4	Betula pubescens	2x	300-350cm	Standard (Selected)	10-12cm	175-200cm	4	RR	rr	rr		
2	Carpinus betulus	2x	300-350cm	Standard	10-12cm	175-200cm	4	RR	rr	rr		
2	Carpinus betulus	2x	425-600cm	Standard (Extra Heavy)	14-16cm	175-200cm	5	RR	rr	rr		
5	Crataegus laevigata 'Paul's Scarlet'	2x	300-350cm	Standard (Selected)	10-12cm	175-200cm	4	B	rr	rr		
3	Fagus sylvatica	2x	300-350cm	Standard	10-12cm	175-200cm	4	RR	rr	rr		
1	Liriodendron tulipifera	4x	425-600cm	Standard (Semi-mature)	30-35cm	Min 200cm	6	RR	rr	rr		
1	Liriodendron tulipifera 'Fastigiatum'	2x	425-600cm	Standard (extra-heavy)	14-16cm	175-200cm	5	RR	rr	rr		
10	Prunus avium	2x	250-300cm	Standard	10-12cm	150-175cm	5	RR	rr	rr		
5	Prunus avium 'Plena'	2x	425-600cm	Standard (extra-heavy)	14-16cm	175-200cm	4	RR	rr	rr		
1	Prunus padus	2x	300-350cm	Standard	10-12cm	175-200cm	4	RR	rr	rr		
6	Prunus padus	2x	425-600cm	Standard (extra-heavy)	14-16cm		7	RR	rr	rr		
2	Pyrus calleryana 'Charadee'	2x	300-350cm	Standard	10-12cm	175-200cm	RR	rr	rr			
3	Quercus robur	2x	200-300cm	Standard	10-12cm		4	RR	rr	rr		
4	Robinia pseudoacacia 'Blossomina'	2x	300-350cm	Standard (Selected)	10-12cm	175-200cm	4	B	rr	rr		
13	Sorbus aria 'Majestica'	2x	300-350cm	Standard	10-12cm	175-200cm	3	RR	rr	rr		
1	Sorbus aucuparia 'Cardinal Royal'	2x	300-350cm	Standard (Selected)	10-12cm	175-200cm	4	RR	rr	rr		
104												
1836												

NB:- Species Rich Native Hedgerow Mix (Trough Grown) is to be supplied by 'best4hedging', or equal and approved. Provided in 1m lengths. Contains 10 different species, of which 8 can be guaranteed to appear in every 6m of hedging. Contains a range of wildflowers within the mix as an understorey, which will be fully knitted together with the hedge itself.



Native Hedgerow Mix
 143nr Cornus sanguinea
 287nr Corylus avellana
 573nr Crataegus monogyna
 143nr Ligustrum vulgare
 143nr Prunus spinosa
 143nr Viburnum lantana

NB:- All proposed tree planting along southern boundary to be 5m away from outside rail

REFER TO CSA/2047/135

LEGEND

- APPLICATION BOUNDARY 10 metres
- EXISTING TREES / VEGETATION
- TREES / VEGETATION REMOVED
- Softworks
- WOODLAND MIX
- HEATHLAND MIX
- SEMI-MATURE TREE
- EXTRA HEAVY STANDARD TREE
- STANDARD TREE
- ORNAMENTAL HEDGE PLANTING
- NATIVE HEDGE PLANTING
- ORNAMENTAL SHRUB / HERBACEOUS / GRASS PLANTING
- CLIMBING SHRUB PLANTING
- AMENITY GRASS SEEDING - 'A22 (Low Maintenance)' seed mix by Geminal Seeds Ltd or equal and approved. 50g / m2, overseed rate; 20g / m2.
- AMENITY GRASS TURF - 'Medallion' turf by Rolawn or equal and approved.
- WILDFLOWER MEADOW MIX - 'WF12 Heavy Clay Soils' by Geminal Seeds Ltd or equal and approved. 5g / m2
- WILDFLOWER MEADOW MIX - 'RE12 Drought Land (U16 Grassland)' by Geminal Seeds Ltd or equal and approved. 5g / m2
- WILDFLOWER MEADOW MIX - 'RE3 River Floodplain / Water Meadow (M8 Grassland)' by Geminal Seeds Ltd or equal and approved. 5g / m2
- MOWN GRASS FOOTPATHS Refer to management plan for details

Notes:-
 1.) For Planting Specification refer to CSA/2047/138
 2.) For Planting Schedule refer to CSA/2047/134

Rev	Date	By	Description
H	13.08.21	LoC	Trees moved 3m back from highway
G	08.03.21	GC	Trees removed opp. Plots 35-38.
F	18.04.18	AM	Trees removed opp. Plots 59-61.
E	18.04.18	AM	Trees adjusted & entry junction revised.
D	14.06.17	AM	Further amendments to Plots 55, 88 & 103.
C	12.06.17	AM	Further amendments to Plots 1 & 145.
B	06.06.17	AM	Amendments to Plots 143-145.
A	21.04.17	TB	Updated site red line boundary.

CSA environmental

Dixies Barns, High Street,
 Ashwell, Hertfordshire SG7 5NT

01462 743647
 ashwell@csaenvironmental.co.uk
 csaenvironmental.co.uk

Project Land to the south of Cockaynes Lane, Alresford

Title Soft