



Fireplace

1no. new shower tray, enclosure etc to replace existing bath. Existing bath removed, packaged, labeled and stored away safely on the castle grounds (Covered under Listed Building Application)

Line walls with new Hygienic Wall panels. (Covered under Listed Building Application)

Replace existing toilet with new (Covered under Listed Building Application)

New cubicle system installed

New stud wall (Covered under Listed Building Application)

Radiator to be removed, packaged, labeled and stored safely on castle grounds. Existing replaced with new (Covered under Listed Building Application)

Form new false wall inside existing bathroom to preserve tiles. New false wall clad in hygienic wall panels. False wall can not be fixed through into tiles under any circumstances (Covered under Listed Building Application)

Remove existing wash hand basin, package, label and store safely on castle grounds. Replace with 2no. new wash hand basins. WHBs to utilise existing pipe-runs to minimise disturbance below floors / in walls. All new services to be concealed behind false wall (Covered under Listed Building Application)

New vinyl flooring to replace existing tiled floor with coved skirting (Covered under Listed Building Application)

PROPOSED BATHROOM ALTERATIONS
BATHROOM NUMBER : F41 (FIRST FLOOR, WEST WING)

SCALE 1 : 20

C	Updated to suit clients comments.	30.11.21
B	Updated to suit clients comments.	30.11.21
A	Updated to show what is covered in each application.	23.11.21
Revision	Description	Date



www.nbda-architects.co.uk Tel 01625 575550

Client PGL HOLIDAYS

Project FORD CASTLE
BERWICK-UPON-TWEED
Drawing PROPOSED BATHROOM
ALTERATIONS EXAMPLE
SHEET 4

Drawing No. 2035IMC-103 Revision C
Scale 1:20@A1 Date 23.07.21 Drawn JWH

This drawing is copyright of N.B.D.A. Ltd. and should not be reproduced without permission. Dimensions should not be scaled off this drawing. All dimensions should be checked on site.

A1 Drawing