



**Notes**

- PIPES**  
110 / 150mm plastic below ground drainage pipe
- DRAINS PASSING THROUGH STRUCTURE**  
Drains to pass through structure above foundation level. Walls to include suitable RC lintels over penetrations
- BEDDING**  
10mm non. dia pea shingle / pipe bedding, 100mm below pipe and 100mm over crown of pipe
- GULLIES**  
Back inlet trapped roddable plastic gullies with plastic grates
- INSPECTION CHAMBERS**  
300mm dia plastic mini-chambers  
600mm dia plastic inspection chambers  
Plastic lids (light duty) in pedestrian areas  
Cast iron lids (heavy duty) in vehicle areas
- FALLS**  
Surface Water Drainage 1:100  
Foul Water Drainage 1:40

<b>Title:</b> Drainage Plan	
<b>Project &amp; Client:</b> Plot 3, Ditchburn Road South Charton Northumberland	
<b>No:</b> 20-42-08	<b>REVISIONS</b>
<b>Scale:</b> 1 : 100	<b>Date:</b> Dec ' 21
	<b>Drawn by:</b>

RICHARDSON

SURVEYING

ARCHITECTURE

17 Aynsley Terrace, Consett, Co. Durham, DH8 5NF

E: info@rsa-ld.co.uk W: www.rsa-ld.co.uk T: 01207 581318