# WOLD ECOLOGY LTD

2 Redwood Gardens, Driffield, East Riding of Yorkshire. YO25 6XA. www.woldecology.co.uk

# Springfields, Turpit Lane, Paull

Preliminary Bat Roost Assessment, 2021.

		Staff Member	Position		
Lead surveyor(s)	:	Chris Toohie M Sc., MCIEEM	Ecologist.		
Report prepared by	:	Chris Toohie M Sc., MCIEEM Ecologist.			
Notes	:	This report contains sensitive information concerning protected species and caution should be exercised when copying and distributing to this parties.			

#### Disclaimer:

This report and its content are copyright © 2021 Wold Ecology Ltd. All rights reserved.

You may not distribute or commercially exploit the content of this report until a non-draft version of this document has been issued and payment in full has been received by Wold Ecology Ltd.

Any unauthorised redistribution or reproduction of part or all the contents of this report will constitute an infringement of copyright.

This report was prepared by Wold Ecology Limited solely for use by Mr and Mrs Nicholson. This report is not addressed to and may not be relied upon by any person or entity other than Mr and Mrs Nicholson for any purpose without the prior written permission of Wold Ecology Ltd. Wold Ecology Ltd, its directors, employees and associates accept no responsibility or liability for reliance upon or use of this report (whether or not permitted) other than by Mr and Mrs Nicholson for the purposes for which it was originally commissioned and prepared.

In producing this report, Wold Ecology Ltd has relied upon information provided by others. The completeness or accuracy of this information is not guaranteed by Wold Ecology Ltd.

#### **DOCUMENT CHECKING**

Issue No.	Date.	Status.	Verified by.
1	04/12/2021	Draft for internal review.	Daniel Lombard B Sc MCIEEM
2	06/12/2021	Draft for client review.	Chris Toohie MSc MCIEEM
3	09/12/2021	Submission of non-draft version for client.	Chris Toohie MSc MCIEEM

This report contains sensitive information concerning protected species and caution should be exercised when copying and distributing to third parties.

# **TABLE OF CONTENTS**

1.0	EXECUTIVE SUMMARY	3
2.0	INTRODUCTION	4
3.0	BACKGROUND TO SPECIES	6
4.0	ASSESSMENT METHODOLOGY	9
5.0	RESULTS	11
6.0	IMPACT ASSESSMENT – in the absence of mitigation	17
7.0	MITIGATION & COMPENSATION	17
8.0	BIRDS	21
9.0	REFERENCES	23
10.0	APPENDICES	24

#### 1.0 EXECUTIVE SUMMARY

1.1 In November 2021, Wold Ecology Ltd was commissioned by Mr and Mrs Nicholson to undertake a preliminary bat roost assessment at Springfields, Turpit Lane, Paull. The site is located at approximate National Grid Reference TA16969 26196, in East Yorkshire.

1.2 The preliminary bat roost assessment results are summarised below:

		Application Site Status	
Proceed with caution, timing constraints  No further surveys required – Stable  No constraints  Barn owl		Birds are afforded various levels of protection and levels of conservation status on a species by species basis. The most significant general legislation for British birds lies within Part 1 of the Wildlife and Countryside Act 1981 (as amended). Under this legislation, it is an offence to, kill, injure or take any wild bird, take, damage or destroy the nest of any wild bird while that nest is in use or being built, take or destroy an egg of any wild bird. All nests should remain undisturbed and intact until after the breeding bird season – mid February to early September. Planning consent for a development does not provide a defence against prosecution under this act.  Bird's nests were observed in the stable (refer to section 8.0).	
		There was no evidence to suggest the presence of bats and in its current condition; it is extremely unlikely that the stable supports a bat roost. It is considered that the proposed development will have none/negligible impacts on bat species.	
		There was no evidence of barn owls <i>Tyto alba</i> roosting in the stable. No further surveys recommended.	

- 1.3 Bat roosts are protected throughout the year, whether bats are present or not.
- 1.4 All bats and their roosts are fully protected under the Wildlife and Countryside Act 1981 (as amended by the Countryside and Rights of Way Act 2000) and are further protected under the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019. Should any bats or evidence of bats be found prior to or during development, work must stop immediately, and Natural England contacted for further advice. This is a legal requirement under the aforementioned acts and applies to whoever carries out the work.
- 1.5 Planning consent for a development does not provide a defence against prosecution under this act.
- 1.6 Habitat enhancement for bats should be implemented as outlined in section 7.0, in order to improve foraging opportunities to bats in the local area.
- 1.7 The data collected to support the output of this report is valid for one year. This report is valid until **December 2022**. After this time, additional surveys need to be undertaken to confirm that the status of the building, as a bat roost, has not changed.

# 2.0 INTRODUCTION


# 2.1 Background Information

- 2.1.1 In November 2021, Wold Ecology Ltd was commissioned by Mr and Mrs Nicholson to undertake a preliminary bat roost assessment at Springfields, Turpit Lane, Paull. The site is located at approximate National Grid Reference TA 16969 26196, in East Yorkshire.
- 2.1.2 The Application Site comprises the following:
  - Stable
- 2.1.3 The proposed development includes the demolition of the stable and the erection of a new annex dwelling.

#### 2.2 Survey Objectives

2.2.1 The site was visited and assessed on 3<sup>rd</sup> December 2021; this was to determine whether the stable on site contained bat roosts or was suitable to support roosting bats during other times of the year. The work involved the following elements:

Survey objective	Yes/No	Comments
Determine presence/absence of roosting bats	Yes	A daytime, visual inspection for bat roosts and roosting bats.  Internal inspection of all roof voids.  An assessment of the on-site suitability for bats and the likelihood of their presence.  Desktop study.
Determine bat usage e.gs maternity roost, summer roosts	Yes	An assessment of whether bats are a constraint to the development.  A bat activity survey has not been undertaken.
Identify swarming, commuting, or mating sites	No	N/A
Other	Yes	The production of a non-technical summary of the legal implications behind bat presence.  Report the findings of the field survey work and identify recommendations for a potential mitigation strategy.
Birds	Yes	The visual inspection also recorded any other visible active/disused nests and bird activity within the building.



#### 3.0 BACKGROUND TO SPECIES

# 3.1 Ecological overview

- 3.1.1 There are seventeen species of bat that currently breed in the UK. There is a wide variety of roost type and ecological characteristics between species and for this reason it is necessary to determine the species of bat and the type of roost resident in a structure prior to development. Roosts are utilised by different species of bat, at different times of year for different purposes i.e. summer, breeding, hibernating, and mating etc. (for more detailed information see section 9.0).
- 3.1.2 Bat populations have undergone a significant decline in the latter part of the 20<sup>th</sup> century; the main factors cited for causing loss and decline include:
  - A reduction in insect prey abundance, due to high intensity farming practice and inappropriate riparian management.
  - Loss of insect-rich feeding habitats and flyways, due to loss of wetlands, hedgerows, and other suitable prey habitats.
  - Loss of winter roosting sites in buildings and old trees.
  - Disturbance and destruction of roosts, including the loss of maternity roosts due to the use of toxic timber treatment chemicals.

#### 3.2 Legal Framework

- 3.2.1 A bat survey is required prior to planning permission being granted for a development, in order to prevent the potential disturbance, injury and /or death of bats and the disturbance, obstruction and/or destruction of their roosting places. This is in compliance with the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019, provision 41 states an offence is committed if a person:
  - (a) Deliberately captures, injures, or kills any wild animal of a European protected species (i.e. bats),
  - (b) Deliberately disturbs wild animals of any such species,
  - (c) Deliberately takes or destroys the eggs of such an animal, or
  - (d) Damages or destroys a breeding site or resting place of such an animal.
- 3.2.2 Section 9 of the Wildlife and Countryside Act (1981) states:
  - It is an offence for anyone without a licence to kill, injure, disturb, catch, handle, possess or exchange a bat intentionally. It is also illegal for anyone without a licence to intentionally damage or obstruct access to any place that a bat uses for shelter or protection.
- 3.2.3 Bat roosts are protected throughout the year, whether or not bats are occupying a roost site.

# 3.3 Planning Policy Guidance

- 3.3.1 A bat survey is a requirement of the Local Planning Authority (LPA), as part of the planning application process. This is specified in the following legislation:
  - National Planning Policy Framework (NPPF): Conserving and Enhancing the Natural Environment.
- 3.3.2 To protect and enhance biodiversity and geodiversity, plans should:
  - a) Identify, map and safeguard components of local wildlife-rich habitats and wider ecological networks, including the hierarchy of international, national

- and locally designated sites of importance for biodiversity; wildlife corridors and stepping stones that connect them; and areas identified by national and local partnerships for habitat management, enhancement, restoration or creation.
- b) promote the conservation, restoration and enhancement of priority habitats, ecological networks and the protection and recovery of priority species; and identify and pursue opportunities for securing measurable net gains for biodiversity.
- 3.3.3 When determining planning applications, local planning authorities should apply the following principles:
  - a) if significant harm to biodiversity resulting from a development cannot be avoided (through locating on an alternative site with less harmful impacts), adequately mitigated, or, as a last resort, compensated for, then planning permission should be refused;
  - b) development on land within or outside a Site of Special Scientific Interest, and which is likely to have an adverse effect on it (either individually or in combination with other developments), should not normally be permitted. The only exception is where the benefits of the development in the location proposed clearly outweigh both its likely impact on the features of the site that make it of special scientific interest, and any broader impacts on the national network of Sites of Special Scientific Interest;
  - c) development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons, and a suitable compensation strategy exists; and
  - d) development whose primary objective is to conserve or enhance biodiversity should be supported; while opportunities to incorporate biodiversity improvements in and around developments should be encouraged, especially where this can secure measurable net gains for biodiversity.
- 3.3.4 The LPA has to assess whether the development proposal would breach Article 12(1) of the Habitats Directive. If Article 12(1) would be breached, the LPA would have to consider whether Natural England was likely to grant a European protected species licence for the development; and in so doing the LPA would have to consider the three derogation tests:
  - a) 'Preserving public health or public safety or other imperative reasons of overriding public interest including those of a social or economic nature and beneficial consequences of primary importance for the environment'.

In addition, the LPA must be satisfied that:

- (b) 'That there is no satisfactory alternative'
- (c) 'That the action authorised will not be detrimental to the maintenance of the population of the species concerned at a favourable conservation status in their natural range'.

#### 3.3.5 Relevant Case Law

- Woolley v Cheshire East Borough (2009).
- R. (Morge) v Hampshire County Council (2011).
- Prideaux v. Buckinghamshire County Council and Fcc Environmental UK Limited (2013).

- 3.3.6 The rulings summarise that if it is clear or perhaps very likely that the requirements of the Directive cannot be met because there is a satisfactory alternative or because there are no conceivable 'other imperative reasons of over-riding public interest' then the authority should act on that and refuse permission.'
- 3.3.7 The conclusion of the judgement is that LPAs must ensure that the option/alternative that best takes into account all the relevant considerations (not just EPS) should be the preferred option assuming that the other two tests specified in Article 16 (1) are also met.
- 3.3.8 The judgements also clarified that it was not sufficient for planning authorities to claim that they had discharged their duties by imposing a condition on a consent that requires the developer to obtain a licence from Natural England. Natural England considers it essential that appropriate survey information supports a planning application prior to the determination. Natural England does not regard the conditioning of surveys to a planning consent as an appropriate use of conditions.

#### 4.0 ASSESSMENT METHODOLOGY

# 4.1 Status of species present in Yorkshire

Bat Specie	UK Status	UK Distribution	Yorkshire Distribution
Common Pipistrelle	Not threatened	Common & widespread	Common & widespread.
Soprano pipistrelle	Not threatened	Common & widespread	Less common than common pipistrelle but fairly widespread.
Nathusius's pipistrelle	Rare	Restricted. Throughout British Isles.	Scarce, bat detector records only.
Brown long-eared	Not threatened	Widespread	Widespread.
Daubenton's	Not threatened	Widespread	Widespread.
Natterer's	Not threatened	Widespread (except N & W Scotland)	Present
Brandt's	Endangered	England and Wales	Few confirmed records.
Whiskered	Endangered	England, Wales, Ireland & S Scotland.	Present.
Noctule	Vulnerable	England, Wales, S Scotland.	Widespread
Leisler	Vulnerable	Widespread throughout the British Isles, except N Scotland.	Rare (locally common in West Yorkshire).
Barbastelle	Rare	England.	No records since 1950's.

Source - http://www.nyorkbats.freeserve.co.uk/bats.htm

# 4.2 Data Review and Desk Study

- 4.2.1 Currently, there is no pre-existing information on bats at the site.
- 4.2.2 Wold Ecology employees, field surveyors and network of associate ecologists have recorded brown long-eared *Plecotus auritus*, noctule *Nyctalus noctula*, Natterer's *Myotis nattereri*, Daubenton's *Myotis daubentonii*, whiskered *Myotis mystacinus*, soprano pipistrelle *Pipistrellus pygmaeus* and common pipistrelle *Pipistrellus pipistrellus* within 5km of the Application Site. Wold Ecology bat records date from 2006 and include over 1500 bat activity surveys.
- 4.2.3 There are no known Natural England development licenses relating to bats within 2km of the Application Site (source www.magic.gov.uk).

# 4.3 Daytime and Visual Inspection

- 4.3.1 The daytime assessment identified whether the area had any signs of occupancy and/or bat usage. This took the form of a methodical search, both internally and externally, for actual roosting bats and their signs. Specifically, the visual survey involved:
  - Assessment for droppings on walls, windowsills and in roof spaces
  - Scratch marks and staining on beams, other internal structures and potential entrance and exit holes
  - Wing fragments of butterfly and moth species underneath beams and other internal structures
  - The presence of dense spider webs at a potential roost can often indicate absence of bats
  - Assessment of crevices and cracks in the buildings to assess their importance for roosting bats

# 4.3.2 Summary of daytime inspection and visual survey

Binoculars, 1million candle power clu-lite torch, 6°C, 100% cloud.  O3/12/21 Stable micro Dart endoscope, Beaufort 0. No Dewalt DW03050 Laser Measure.  3.9m telescopic ladders	Date of each survey visit	Structure reference/location	Equipment used/available	Weather
	03/12/21	Stable	clu-lite torch, micro Dart endoscope, Dewalt DW03050 Laser Measure.	Beaufort 0. No

Comments (to include # of surveyors used for each visit): 1 surveyor undertook the visual inspection.

#### Personnel:

Chris Toohie (Class 2 bat license - 2019-44215-CLS-CLS and RC027) – 3<sup>rd</sup> December 2021

#### 4.3.3 Personnel

Chris Toohie MCIEEM	Project Manager of Wold Ecology with over 15 years' experience surveying bats. Chris has conducted over 900 bat activity surveys since 2006, held over 135 Natural England development licenses and is one of only 221 (November 2021) Natural England Registered Consultants who can hold a Bat Mitigation Class Licence.	RC027 and 2019-44215- CLS-CLS
------------------------	--	-------------------------------------

#### 5.0 RESULTS

# 5.1 Habitat description

- 5.1.1 The Application Site is located on the northern boundary of Paull village, in a rural location. The Application Site is less than 1 ha and is immediately surrounded by arable/grazed pasture and residential dwellings with mature private gardens. There are no other structures within the red line boundary which have bat roosting potential.
- 5.1.2 Adjacent Landscapes
- 5.1.2.1 The village of Paull is located adjacent to the River Humber and is surrounded by mixed agricultural land dominated by arable with grazed pastures and estuarine habitats. Woodland cover within 2km is low but occurs as fragmented shelterbelts adjacent to farms, small holdings and Paull Fort. Whilst the Application Site is not directly connected to any optimum bat foraging habitat, connectivity within 500m is provided by hedgerows that bound most pf the large arable fields.
- 5.1.2.2 Wold Ecology concludes that the adjacent habitats could be used by small numbers of commuting and foraging bats. These habitats are not extensive and are similar to surrounding garden/arable habitats and consequently, the Application Site and adjacent habitats are not considered to be integral to the favourable conservation status of local bat populations.
- 5.1.3 Habitat Summary
- 5.1.3.1 A summary of the surrounding habitat is (radius of < 2km from the site):
  - Buildings farm buildings and residential properties
  - Paull Fort
  - Paull Holme Strays Nature Reserve
  - Salt End Chemical Works
  - Hedgerow
  - Hedgerows with trees
  - Mature trees and woodland
  - Arable
  - Mature private gardens
  - Ponds and watercourses
  - Humber Estuary
  - River Humber
  - Newton Garth Drain
  - Thorngumbald Drain
  - Hedon Haven
  - Grazed pasture



NORTH\_

**Scale:** 1:25,000

**Drawing title:** Aerial Photograph

**KEY** 

Application Site

# WOLD ECOLOGY LTD



2 Redwood Gardens Driffield East Yorkshire YO25 6XA

T: 01377 200242 E: info@woldecology.co.uk W: www.woldecology.co.uk

# 5.2 Building description

- 5.2.1 The bat survey and assessment targeted the following (see section 5.5):
  - a. **Stable** is single storey and comprises breeze block and cement fibre board walls and a pitched roof covered with corrugated cement fibre boards. The roof is supported by smooth sawn timbers and is not lined. The stable is used for storage.
- 5.2.2 **Stable** (see 5.5 plates 1 3) no roosting opportunities were present within the fabric of the building due to the following:
  - Gaps beneath the ridges are greater than 50mm and are unsuitable to support roosting bats.
  - The timber frame and tongue and groove panels on the gables are tight fitting,
  - There are no gaps in the blockwork, wall sheets or corrugated cement fibre board roof coverings which are suitable for roosting bats.
  - The eaves are tight fitting and there are no gaps in the internal/external mortar suitable for roosting bats.
  - The timber doors and timber window frames were tight fitting.
  - There are no gaps in the roof structure to support roosting bats.
  - No evidence of bats was observed.
  - The stable has been assessed as having a NEGLIGIBLE SUITABILITY to support bats.
- 5.3 Based on the field survey and the criteria in table 4.1 (Bat Surveys for Professional Ecologists 3<sup>rd</sup> Edition, p35. Bat Conservation Trust, 2016), the Application Site and studied building has the following suitability for bats:

	Negligible	Low	Moderate	High
Application Site habitats (<2km)		X		
Stable	X			

Table 4.1 Guidelines for assessing the potential suitability of proposed development sites for bats, based on the presence of habitat features within the landscape, to be applied using professional judgement. Description Suitability Roosting habitats Commuting and foraging habitats Negligible habitat features on site likely to be used by Negligible habitat features on site likely to be used Negligible roosting bats. by commuting or foraging bats. Habitat that could be used by small numbers of Low A structure with one or more potential roost sites that could be used by individual bats opportunistically. commuting bats such as a gappy hedgerow or However, these potential roost sites do not provide unvegetated stream, but isolated, i.e. not very well enough space, shelter, protection, appropriate conditions<sup>a</sup> connected to the surrounding landscape by other and/or suitable surrounding habitat to be used on a habitat. regular basis or by larger numbers of bats (i.e. unlikely to Suitable, but isolated habitat that could be used by be suitable for maternity or hibernation<sup>b</sup>). small numbers of foraging bats such as a lone tree A tree of sufficient size and age to contain PRFs but with (not in a parkland situation) or a patch of scrub. none seen from the ground or features seen with only very limited roosting potential.c Continuous habitat connected to the wider Moderate A structure or tree with one or more potential roost sites that could be used by bats due to their size, shelter, landscape that could be used by bats for commuting such as lines of trees and scrub or linked back protection, conditions<sup>a</sup> and surrounding habitat but unlikely to support a roost of high conservation status gardens. (with respect to roost type only - the assessments in this Habitat that is connected to the wider landscape table are made irrespective of species conservation that could be used by bats for foraging such as status, which is established after presence is confirmed). trees, scrub, grassland or water. High A structure or tree with one or more potential roost sites Continuous, high-quality habitat that is well that are obviously suitable for use by larger numbers of connected to the wider landscape that is likely to be bats on a more regular basis and potentially for longer used regularly by commuting bats such as river periods of time due to their size, shelter, protection, valleys, streams, hedgerows, lines of trees and conditions<sup>a</sup> and surrounding habitat. woodland edge. High-quality habitat that is well connected to the wider landscape that is likely to be used regularly by foraging bats such as broadleaved woodland, treelined watercourses and grazed parkland. Site is close to and connected to known roosts.

Source - Bat Surveys for Professional Ecologists – 3rd Edition, p35. Bat Conservation Trust, 2016.

# 5.4 Results of Activity Surveys

5.4.1 There is no current (with the previous 2 years) bat activity survey data available for this site.

# 5.5 Photographs of key features – December 2021

Plate 1 – north elevation and west gable.



Plate 2 – south elevation.



Plate 3 – internal roof void



5.6 Summary of field surveys conducted in 2021

Date	Type of survey	Results	Building Dimensions (m)			
Dute		Results	L	W	Н*	
03/12/21	Habitat assessment	Wold Ecology concludes that the adjacent habitats could be used by small number of commuting and foraging bats. These habitats are not extensive and are similar surrounding garden/arable habitats and consequently, the Application Site and adjacent habitats are not considered to be integral to the favourable conservation status of local bat populations.				
03/12/21	Visual inspection.	Stable There were no signs of roosting bats or bat activity, and the stable has no features to support roosting bats. Consequently, the building has a NEGLIGIBLE SUITABILITY to support bats (see 5.3 plates 1 - 3).	14.7	9.0	3.2	

<sup>\*</sup> Height from ground floor to ridge

#### 5.7 Interpretation and Evaluation of Survey Results

#### 5.7.1 Presence/absence

5.7.1.1 Currently, from the data collected during one visit, the likelihood that bats are present within the stable to be demolished is negligible. This is supported by the fact that the building is in good condition with no roosting opportunities for bats observed. The daytime assessment detected no signs of bat usage or activity and consequently, the impact to bats from the demolition of the stable is considered to be **negligible**.

#### 5.7.2 Site Status Assessment

5.7.2.1 The assessment is based on one daytime survey conducted in December. During this time of year bats are usually in hibernation, therefore, bats are inactive. Consequently, it is not always possible to fully determine whether bats are actually roosting in the stable. However, due to the absence of suitable features likely to support bats, the studied stable has been assessed as having a NEGLIGIBLE SUITABILITY for bats.

#### 5.7.3 Constraints

5.7.3.1 There are no survey constraints.

# 6.0 IMPACT ASSESSMENT – in the absence of mitigation

It is not always possible to predict the full pre-, mid-development and long-term impacts on bat populations based on a single daytime survey conducted in December. Based on the current information, the studied stable does not support a bat roost. However, bats are by nature highly mobile and secretive mammals and there is always a possibility that bats may turn up at a site at any time. Therefore, taking into consideration all the information collected to date, it has been determined that the proposed development would pose none/negligible impacts to local bat populations.

#### 7.0 MITIGATION & COMPENSATION

# 7.1 Legal Protection

- 7.1.1 Legal obligations towards bats are generally concerned with roost protection. All developments, known to contain bat roosts, require a development licence from Natural England. Under the Wildlife and Countryside Act (1981) and the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019, it is an offence for anyone without a licence to:
  - Deliberately take, injure or kill a wild bat
  - Intentionally or recklessly disturb a bat in its roost or deliberately disturb a group of bats.
  - Damage or destroy a place used by bats for breeding or resting (roosts) (even if bats are not occupying the roost at the time)
  - Possess or advertise/sell/exchange a bat of a species found in the wild in the EU (dead or alive) or any part of a bat.
  - Intentionally or recklessly obstruct access to a bat roost.
- 7.1.2 Planning consent for a development does not provide a defence against prosecution under these acts.
- 7.1.3 Bat roosts are protected throughout the year, whether bats are present or not.
- 7.1.4 As no bat roosts or signs of bat activity were detected during the daytime inspection and the stable has negligible suitability to support roosting bats, building work can commence with adherence to the following Method Statement (see 7.2 below).
- 7.2 Method Statement
- 7.2.1 This statement should be copied to contractors and all those involved with demolition, timber treatment and building works, whose work may affect bats and their roosts on site.
- 7.2.2 Timing
- 7.2.2.1 There are no mandatory timing constraints as roosting bats have not been found and the stable has negligible suitability to support roosting bats.
- 7.2.3 In the highly unlikely event that bats are discovered:
  - Immediately stop the work that you are undertaking.
  - Do not expose the bat or cause it to fly out of the roost on its own accord.

- Contact Wold Ecology on 01377 200242 or 07795 071504 for advice.
- Advise colleagues in the vicinity of your work why you have stopped and advise them to be aware of the potential for bats being disturbed, injured or killed.
- Immediately report the matter to your site manager/line manager who will inform relevant personnel.
- Grounded bats must be carefully placed in a lidded, ventilated box with a piece of clean cloth and a small shallow container with some water. The box must be kept in a safe and quiet location.
- Any underweight or injured bats must be taken into temporary care by an experienced bat carer and looked after until such time that the bat can be transferred to a suitable replacement roost at the same site, or weather conditions are suitable for release at the same site.
- 7.2.4 Bats will only be handled by a licensed bat ecologist, wearing gloves, who has received a rabies vaccination. The bat will be placed either into a holding box, with water provided, and re-released close to the farm at dusk, or placed into a bat box located on site.
- 7.2.5 Injured bats will be taken into care (as directed by the Bat Workers Manual, section 7.3, pages 64 66:  $3^{rd}$  edition 2004) and fed and cared for until such time when conditions are suitable (night time temperature are  $>6^{\circ}$ C) for them to be released at dusk in the mitigation area.

#### 7.3 Bat boxes

- 7.3.1 Specially designed bat boxes can be located on site. Schwegler Bat Boxes are recommended and well tested boxes. The following bat boxes provide additional roost habitats and are available from Wold Ecology:
  - The **2FN** bat box has two entrances one at the front and one at the rear against the tree. Bats often creep into the rear entrance but leave by the front. It has a domed roof to allow the bats to form roosting clusters for warmth and this bat box is also designed to be effective against small predators and excludes draughts and light. Due to the opening on the bottom, this bat box does not require cleaning.
  - The **1FQ** is an attractive box designed specifically to be fitted on the external wall of a house, barn, or other building. Equally appealing to bats as a roost or a nursery, it features a special porous coating to help maintain the ideal temperature inside along with a rough sawn front panel to enable the bats to land securely.
  - Bat Tube (**1FR** and **2FR**) system. The tube is designed to meet behavioural requirements of the types of bats that roost in buildings i.e. pipistrelle spp. This design can be installed flush to external walls and beneath a rendered surface.
  - Alternative bat boxes are available, these should comprise woodcrete and not timber.
- 7.3.2 The majority of these boxes are self-cleaning as they are designed so that the droppings fall out of the entrance. This reduces the possibility of smell during the summer months. For more information on designs and installation of bat boxes see: www.schwegler-natur.de and www.bct.org.uk.

7.3.3 Wold Ecology recommends that at least 1 bat box is sited on buildings or trees on site. Bat boxes should be erected on south, east or west elevations; 3-5 metres above ground level or close to roof lines.

# 7.4 Lighting

- 7.4.1 Lighting has a detrimental effect on bat activity; many bats will actually avoid areas that are well lit. Lighting can cause habitat fragmentation by preventing bats from commuting between roosts and foraging grounds (A.J Mitchell-Jones 2004).
- 7.4.2 It is recommended that a lighting consultant is employed to design a lighting plan based on the following principles:
  - Luminaire and light spill accessories Lighting should be directed to where it is needed, and light spillage avoided. This can be achieved by the design of the luminaire and by using accessories such as hoods, cowls, louvres and shields to direct the light to the intended area only.
  - If applicable, the height of lighting columns in general should be as short as is possible as light at a low level reduces the ecological impact. However, there are cases where a taller column will enable light to be directed downwards at a more acute angle and thereby reduce horizontal spill. For pedestrian lighting, this can take the form of low level lighting that is as directional as possible and below 1 lux at ground level.
  - Aim for lighting column of 5m or less, hooded and cowled to prevent light spill, for main lighting columns.
  - All luminaires should lack UV elements when manufactured. Metal halide, fluorescent sources should not be used.
  - LED luminaires should be used where possible due to their sharp cut-off, lower intensity, good colour rendition and dimming capability.
  - A warm white spectrum (ideally <2700Kelvin) should be adopted to reduce blue light component.
  - Luminaires should feature peak wavelengths higher than 550nm to avoid the component of light most disturbing to bats (Stone, 2012).
  - Internal luminaires can be recessed where installed in proximity to windows to reduce glare and light spill.
  - The use of specialist bollard or low-level downward directional luminaires to retain darkness above can be considered.
  - Only luminaires with an upward light ratio of 0% and with good optical control should be used.
  - Luminaires should always be mounted on the horizontal, i.e. no upward tilt.
  - Any external security lighting should be set on motion-sensors and short (1min) timers.
  - As a last resort, accessories such as baffles, hoods or louvres can be used to reduce light spill and direct it only to where it is needed.
  - Light spill can be successfully screened through soft landscaping and the installation of walls, fences and bunding
- 7.4.3 At this site, new lighting design will ensure lights will **not** be mounted where they will shine directly on to bat boxes, or the surrounding hedgerow habitat used by foraging and commuting bats. A light intrusion lux level besides hedgerow along the eastern boundary will be 1 lux or below.

# 7.5 Timber treatment

7.5.1 It is good practice, where bats may come into contact with roof timbers, to carry out timber treatment using Permethryn type chemicals on the Natural England list of approved safe chemicals. New pre-treated timbers i.e. tanalised timber will be allowed to dry thoroughly before use, if applicable. A list of Natural England approved paints and timber treatments is available at https://www.gov.uk/guidance/bat-roosts-use-of-chemical-pest-control-products-and-timber-treatments-in-or-near-them

#### 8.0 BIRDS

- 8.1 Birds are afforded various levels of protection and levels of conservation status on a species by species basis. The most significant general legislation for British birds lies within Part 1 of the Wildlife and Countryside Act 1981 (as amended). Under this legislation, it is an offence to, kill, injure or take any wild bird, take, damage or destroy the nest of any wild bird while that nest is in use or being built, take or destroy an egg of any wild bird.
- 8.2 The daytime assessment identified whether the studied building had any signs of residency and/or barn owl usage. Specifically, the visual survey involved:
  - An assessment of the suitability of buildings or stone feature to enable access for breeding barn owls.
  - A thorough check for pellets, feathers or signs of old nest remains in the form of pellet debris and/or old broken egg shells.
- 8.3 The visual inspection also recorded any other visible active/disused nests and bird activity within the building.
- 8.4 Field survey results
- 8.4.1 There was no evidence of barn owls *Tyto alba* roosting in the stable. No further surveys are recommended.
- 8.4.2 The following nests were observed:

Species/nest type	Number	Location	Comment
Small passerine*	3	Stable	Inactive
Swallow Hirundo rustica	2	Stable	Inactive

<sup>\*</sup> Small passerine nest primarily moss, feathers, leaves and vegetation suitable for tits, blackbird *Turdus merula*, robin *Erithacus rubecula*, wren *Troglodytes troglodytes* etc.

- 8.5 Biodiversity Gains and Recommendation
- All nests should remain undisturbed and intact until after the breeding bird season mid February to early September. Any destructive building works (e.g. demolition, roof stripping, internal conversion, pointing of masonry etc.) and removal of vegetation should be undertaken outside of the bird nesting season which is between the months of mid-September and early February inclusive or be carefully checked by an ecologist to confirm no active nests are present. If nesting birds are found during the watching brief, destructive works will need to stop until the young have fledged.
- 8.5.2 In order to increase nesting opportunities for birds, it is recommended that Schwegler bird boxes are erected throughout the site. Local Authority guidance recommends that 25% of houses within a development should contain a bird box.

<sup>\*\*</sup> Larger nest primarily twigs suitable for wood pigeon *Columba palumbus*, feral pigeon *Columba livia*, collared dove *Streptopelia decaocto*, Jackdaw *Corvus monedula* etc.

8.5.3 Bird boxes will target species of conservation concern. A summary of recommended bird boxes are listed below:

Name	Description	Number
Schwegler swift box #16S	Building box for eaves	1

- 8.5.4 Boxes should be placed so that the entrance does not face the prevailing wind, rain and strong sunlight. The sector from north to south east should be used, with south facing boxes positioned in more shaded areas.
- 8.5.5 Many species will use boxes at a wide variety of heights however to give the box protection in areas with a lot of human or mammalian predator activity they should be placed approximately 3-4 metres above ground level. A clear flight path should be available to and from the nest box.

#### 9.0 REFERENCES

Bat Conservation Trust. 'Bats in Churches' leaflet.

Bat Conservation Trust. 'Bat Surveys for Professional Ecologists, 3<sup>rd</sup> Edition (2016).

Bat Conservation Trust. 'Biodiversity for Low and Zero Carbon Buildings: A Technical Guide to New Build'. Dr Carol Williams, 2010.

Mitchell-Jones A.J. (2004). 'Bat Mitigation Guidelines'. English Nature, Peterborough.

English Nature (2003). 'Focus on Bats'.

English Nature (1993) 'Bats in Roofs; A Guide for Surveyors'.

English Nature Northumbria Team (2004) 'Bat surveys for development proposals in North-East England'. English Nature.

Habitat Management for Bats. (2001). A guide for land managers, land owners and their advisors. JNCC.

Horacek, I. Notes on the ecology of bats if the genus Plecotus. Vestnik Cestolslovenske Spolecnosti Zoologiche.

Mitchell-Jones, A.J. & McLeish, A.P. (1999) 'The bat workers' manual' 2<sup>nd</sup> edition. Joint Nature Conservation Committee.

Mitchell-Jones, A.J. (2004) 'Bat mitigation guidelines.' English Nature, Peterborough.

The Bat Conservation Trust www.bats.org.uk Much additional information is available on bats at this website.

Thomas, D.W. 1995. The physiological ecology of hibernation in vespertilionid bats. Symposia of the Zoological Society of London 67: 233–244.

Town and Country Planning Association 'Biodiversity Positive: Eco-towns biodiversity positive'. 2011. http://www.tcpa.org.uk/pages/biodiversity.html

UK Mammals: Species Status and Population Trends. JNCC / Tracking Mammals Partnership. 2005

www.bats.org.uk

https://www.gov.uk/government/collections/bat-licences

#### 10.0 APPENDICES

# 10.1 Background to Bats - Bat Biology.

- Bats roost in a variety places such as caves, mines, trees, and buildings. Woodlands, pasture, ponds and slow flowing rivers or canals provide suitable feeding areas for bats as they support an abundance of suitable insect forage. Bats tend to feed during the first two to three hours after sunset and again before dawn, when insect activity is at its most intense (JNCC 2004).
- Bat activity over the course of a year reflects the seasonal climate and the availability of food as follows (The Bat Conservation Trust, undated):

**January - March** - insect prey is scarce, and bats will hibernate alone or in small groups.

**April - May** - insects are more plentiful and bats will become active. They may become torpid (cool and inactive) in bad weather. Females will start to form groups and will roost in several sites.

**June - July** - females gather in maternity roosts and give birth to young, which are suckled for several weeks. Males roost alone nearby.

**August - September** – mothers leave the roost before the young. Bats mate and build up fat for the winter.

**October - December** – Bats search for potential hibernacula. They become torpid for longer periods and then hibernate.

- 10.1.3 Bats do not stay in the same roost throughout the year. They have different requirements of roosts at different times of the year. During late April/May the bats leave their winter roosts and the females come together to form 'nursery roosts', these usually consists of pregnant females along with a few non-breeding and immature females. At this time, the males roost either singly or in small numbers. The single offspring is born during late June early July and can fly within 3-5 weeks.
- 10.1.4 Typical roost site are cracks and crevices in buildings and other structures but more typically under hanging tiles, slates, soffits and cavity walls of fairly modern buildings or holes and splits in trees.
- 10.1.5 The conditions needed by bats for hibernation require the maintenance of a relatively stable low temperature  $(2 6^{\circ})$ . Suitable sites include; old trees, caves, cellars, tunnels, and icehouses.
- 10.1.6 Whilst the summer roosts consist of single species (although 2 3 species can be found within one large structure but occupying separate roost sites), winter sites often consist of 4 6 different species of bat, although there is often niche separation.
- 10.1.7 Bats have a complex social structure based on 'meta populations' and also utilise other transitional or intermediate roost sites. The several different types of roost, which bats occupy throughout the year, are as follows:
  - **Day roost**: a place where individual bats, or small groups of males, rest or shelter in the day but are rarely found by night in the summer.
  - Night roost: a place where bats rest or shelter in the night but are rarely found in the day. May be used by a single individual on occasion or it could be used regularly by the whole colony.

- **Feeding roost**: a place where individual bats or a few individuals rest or feed during the night but are rarely present by day.
- Transitional/occasional roost: used by a few individuals or occasionally small groups for generally short periods of time on waking from hibernation or in the period prior to hibernation.
- **Swarming site**: where large numbers of males and females gather during late summer to autumn. Appear to be important mating sites
- Mating sites: sites where mating takes place from later summer and can continue through winter.
- **Maternity roost**: where female bats give birth and raise their young to independence.
- **Hibernation roost**: where bats may be found individually or together during winter. They have a constant cool temperature and high humidity. These have to be cold and free from any temperature fluctuation with high humidity. The coldness enables bats to lower their body temperature and become torpid. This saves a lot of energy, enabling them to survive on the fat stores within their bodies that they have built up throughout the summer.
- **Satellite roost**: an alternative roost found in close proximity to the main nursery colony used by a few individual breeding females to small groups of breeding females throughout the breeding season.
- 10.1.8 The main threats to bats include:
  - Habitat loss (e.g. deforestation)
  - Loss of feeding areas as a result of modern forestry and farming practices.
  - Use of toxic agrochemicals and remedial timber treatment chemicals.
  - Disturbance and damage to bat roosts.
- 10.1.9 Bats have been in decline both nationally and internationally during the latter part of the 20<sup>th</sup> Century. Bats require a variety of specific habitats in order to meet the basic needs of feeding, breeding, and hibernating and are therefore extremely vulnerable to change such as the loss of flight lines through the removal of hedgerows. It is thought that even the two most common and widespread bats, the common pipistrelle and the soprano pipistrelle, have declined by an estimated 70% (1978-1993 figures). There are a number of bat species, which are now considered seriously threatened with one species, the greater mouse-eared bat being classed as extinct as it is no longer breeding in the U.K.
- 10.1.10 All European bats are listed in Annex IV of the EC Directive 92/94/EEC 'The Conservation of Natural Habitats and of Wild Fauna and Flora' as needing "strict protection". This is translated into British Law under the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019. British bats are included under Schedule 5 of the Wildlife & Countryside Act 1981. They can therefore be described as a 'fully protected' or 'protected' species.
- A summary of the legal protection afforded to bats under both European and British law is provided by the Bat Conservation Trust (BCT, 2010):

  'All European bat species and their roosts are listed in Annex IV of the EC Directive 92/94/EEC 'The Conservation of Natural Habitats and of Wild Fauna and Flora' as needing "strict protection". This is implemented in Britain under the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019. In summary, in the UK, it is an offence to:
  - Deliberately capture, injure, or kill a bat;

- Deliberately disturb a bat in a way that would affect its ability to survive, breed
  or rear young, hibernate or migrate or significantly affect the local distribution
  or abundance of the species;
- Damage or destroy a roost (this is an absolute offence); and
- Possess, control, transport, sell, exchange or offer for sale/exchange any live or dead bat or any part of a bat.'
- 10.1.12 The species is also listed in Appendix II of the Bonn Convention (and its Agreement on the Conservation of Bats in Europe) and Appendix II of the Bern Convention (and Recommendation 36 on the Conservation of Underground Habitats). Although these are recommendations and not statutory instruments.
- 10.1.13 Natural England is the Government body responsible for nature conservation. Local planning authorities must consult them before granting planning permission for any work that would be likely to result in harm to the species or its habitat. Natural England issue "survey" licenses for survey work that requires the disturbance or capture of a species for scientific purposes. They also issue "conservation" licenses that are required for actions that are intended to improve the natural habitat of a European protected species or to halt the natural degradation of its habitat.
- 10.1.14 'Development' licences are issued by Natural England for any actions that may compromise the protection of a European protected species, including bats, under the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019. This includes all developments and engineering schemes, regardless of whether or not they require planning permission.
- 10.1.15 The UK Biodiversity Action Plan states that although the pipistrelle is one of the most abundant and widespread bat species in the UK, it is still thought to have undergone a significant decline in the latter part of this century. The main factors cited for causing loss and decline include:
  - A reduction in insect prey abundance, due to high intensity farming practice and inappropriate riparian management.
  - Loss of insect-rich feeding habitats and flyways, due to loss of wetlands, hedgerows, and other suitable prey habitats.
  - Loss of winter roosting sites in buildings and old trees.
  - Disturbance and destruction of roosts, including the loss of maternity roosts due to the use of toxic timber treatment chemicals.

#### 10.2 Significance of bat roosts, appraising the nature conservation value;

10.2.1 The significance of bat roosts should be appraised against the following table. Where the extent of the bat roost is unclear a precautionary approach should be taken in evaluating the significance of the roost and the highest potential category should be selected.

Table 9.2.1 Appraisal of significance of bat roosts.

Scale	Summary	Examples		
International	Any significant roosting sites for	Barbastelle bat roosts are only known		
	European Annex 2 species	applicable feature in East Anglia.		
National	Any roosts qualifying as SSSI under the EN criteria.	Details of criteria are given in		

		9.1.2 Site Selection Guidelines for Biological SSSI's.		
Regional	Any significant bat roosts and features, equivalent in interest to qualifying a site as a Country Wildlife Site.	Breeding and hibernation roosts of most species.		
Local	All other sites supporting feeding bats as Wildlife and Countryside Act protected species.	Bats foraging within a structure, night roosts and minor transition roosts.		

Summary of conservation significance of roost types (Bat Mitigation Guidelines, 2004).

	Development effect	Scale of impact		
Roost type	_	Low	Medium	High
Maternity	Destruction			✓
	Isolation caused by fragmentation			✓
	Partial destruction; modification		✓	
	Temporary disturbance outside breeding season	<b>√</b>		
	Post-development interference			✓
Major hibernation	Destruction			✓
	Isolation caused by fragmentation			✓
	Partial destruction; modification		✓	
	Temporary disturbance outside hibernation season	✓		
	Post-development interference			✓
Minor hibernation	Destruction			✓
	Isolation caused by fragmentation			✓
	Partial destruction, modification		✓	
	Modified management		✓	
	Temporary disturbance outside hibernation season	✓		
	Post-development interference		✓	
	Temporary destruction, then reinstatement	✓		
Mating	Destruction		✓	
	Isolation caused by fragmentation		✓	
	Partial destruction	<b>✓</b>		
	Modified management	✓		
	Temporary disturbance	✓		
	Post-development interference	✓		
	Temporary destruction, then reinstatement	✓		
Night roost	Destruction	✓		
	Isolation caused by fragmentation	✓		
	Partial destruction	✓		
	Modified management	✓		
	Temporary disturbance	✓		
	Post-development interference	✓		
	Temporary destruction, then reinstatement	✓		

**NB** This is a general guide only and does not take into account species differences. Medium impacts, in particular, depend on the care with which any mitigation is designed and implemented and could range between high and low.