


**PROPOSED SIDE ELEVATION**



**PROPOSED REAR ELEVATION**



**PROPOSED SIDE ELEVATION**

**GENERAL**

All works to comply with Building Regulations 2000 and associated legislation and to the satisfaction of the Local Authorities Building Control Officer. All building materials to comply with BSS and used in accordance with the relevant Codes of Practice. All structural timber to be C16 or C24 grade.  
All openings to be fitted with vertical and horizontal DPM. All lintels to have 150mm end bearing and 1/2 hour fire resistance. All new electrical work to be 13A ring main and lighting circuit to comply to IEE standards and to clients instructions.

**FOUNDATIONS**

Subject to suitable ground conditions, new strip foundations to comply to BS:8004 on suitable loadbearing strata and to the satisfaction of the Local Authority Building Control Officer. Top of foundations to be min 750mm below ground level and reinforced with A193 mesh with 50mm cover top and bottom. Foundations to be taken below invert levels of existing drains. Check existing foundations and underpin if necessary, at staggered stages. Any deviation from a strip foundation may require design and calculations from Structural Engineer.

NOTE - Should the Builder prefer using a raft foundation in lieu of a strip foundation, they must provide details and calculations to the LA Building control officer prior to commencement of works.

**EXTERNAL WALL**

300mm cavity walling shall comprise of an outer leaf of facing brickwork to match existing, an inner leaf of 100mm thick blockwork "Toplite" or similar, 100mm Dritherm full fill insulation taken 225mm below dpc providing minimum U-Value of 0.3W/m2K.

Stainless steel vertical twist type wall ties to BS 1243:1978 every 750mm horizontally and 450mm vertically and ties within 150mm of openings to be at 225mm crs vertically.

Lateral restraint provided by means of 30mm x 5mm galvanised steel holding down straps @ 2m centres maximum and carried across at least 3 timber members.

Vertical strapping required to joists / wallplates by 30mm x 5mm galvanised steel holding down straps @ 2m centres maximum. All masonry below ground level externally and dpc level internally shall be either Class B engineering bricks or loadbearing solid type A blocks.

Cavity fill below ground level shall be ordinary prescribed mix to BS 5328, grade C10P.

All cavities to be continuous, all openings trimmed with Kingspan Thermabate (or similar) insulated cavity closers. Where pipes pass through wall PC Lintel to be provided and 50mm compressible material to surround pipework. Dpc.s to all openings shall be a minimum width of 150mm Horizontal Dpc located 150 mm above ground level. Blockwork walls shall be finished in 12.5mm Gyproc wallboard on Dri-wall dabs with all joints to be taped and sealed.

**EFFICIENCY LIGHT FITTINGS**

Provide lighting fittings as tabled below to be fixed lighting that only accepts lamps having a luminous efficiency greater than 45 lumens per circuit watt and a total output greater than 400 lamp lumens. Such fittings would include fluorescent tubes and compact fluorescent lamps but not GLS tungsten lamps with bayonet cap or Edison screw bases.

Number not less than three per four of all the light fittings.

**ABOVE GROUND DRAINAGE**

All waste pipes and fittings from sanitary appliances are to be upvc to BS5255: 1076. Branch pipes and vent pipes to be UPVC to BS 4514 : 1983. All pipes to be fitted with rodding access to all changes of direction and at junctions. All wastes to be fitted with 75 mm deep seal traps.

**SMOKE DETECTORS**

Smoke detectors are to be installed in complete compliance with Approved Document B1, Section 1 of the Building Regulations. Multiple installations are to be wired together on a separate circuit in accordance with the current IEE regulations.

**ROOF CONSTRUCTION**

Approved single lap slates to match existing on battens on one layer of roofing felt 1F to BS 747 on trussed rafters @ 600mm crs approx. Rafters are to be supported on 100 x 65mm wallplates at base and held down by means of galvanised mild steel restraint straps type BAT M305 or similar, 30 x 5 mm and 100 x 650 mm twice fixed to top of wallplate using No. 12x50mm countersunk head woodscrews and plugged and screwed to blockwork. 30 x 5mm Galvanised steel restraint straps to be installed at gable wall and 75 x 38 mm sw noggins to be between the rafters at each strap. Spacing of straps to be 1800mm centres max. and straps to be installed at ceiling level and up the slope of the roof and carried across end 3 rafters.

BS 5250 requirement for a ventilation gap equivalent to a 5mm slot for the length of the ridge to be provided Continuous 10mm ventilators at eaves and ducting trays to rafters for airflow in roof. Roof bracing shall be installed horizontally and diagonally and in strict accordance with engineers design and calculations.

Valley base formed using 19mm timber supports cut between rafters and supported by 38 x 25 battens nailed to rafters . Top surface of board must be flush with top of trussed rafters Code No 4 lead to be laid and dressed in lengths not exceeding 1.5m on 4mm plywood sheathing Min 125mm width provided between vertical faces of valley.

Roof bracing shall be installed horizontally and diagonally and in strict accordance with BS 5268: Part 2 1985 and manufacturer's instructions.

**FIRST FLOOR CONSTRUCTION**

22mm Weyroc to BS 5669 to be glued and screwed to 200 x 50 C16 joists @ 600mm crs approx and built into brickwork both ends. Herring bone strutting spaced at mid span of floor joists. 15mm Plasterboard and skim to u/side with 100mm Quilt insulation in floor void

**GROUND FLOOR CONSTRUCTION**

22mm V313 Weyroc to BS:5669 on 125 x 50mm C16 Joists @ 400mm crs approx. fixed onto 100 x 65mm wallplate on DPC on honeycombed sleeper walls @ 2m crs max. on 100mm oversite concrete on 2000 gauge visqueen lapped and taped to DPC on 25mm sand blinding on 125mm approved consolidated hardcore.

120mm Kingspan TF70 insulation on battens between joists providing min 0.22 W/m2K.

Trunked airbricks to allow under floor ventilation.

150mm clear between top of oversite and u/side of joist.

Ventilation must be maintained to the existing house sub floor through the new ground supported floor. This can be achieved using 100mm diameter pipes and telescopic vents.

**RADIATORS**

All new radiators to be provided with Thermostatic valves. Client to agree locations with Builder prior to commencement of works.

**WINDOWS**

New windows to be double glazed in UPVC frame to match existing to pattern shown and are to be supplied pre-fitted with permanently fixed controllable trickle ventilators having an area not less than 8000 square millimeters.

All glazing below 800mm above floor level, and in doors or 300mm adjacent doors, to be either toughened or laminated safety glass in accordance with BS 6206:1981.

Soft coat Low E glass to inner skin.

Certification to verify Part L1 compliance 1.8W/m2K) to be issued from suppliers.

New UPVC windows to First Floor Bedrooms to be fitted with an unobstructed openable area of 0.33m2 with minimum dimensions of 450mm high x 450mm wide (i.e clear opening of 750 x 450mm) Window not to be fitted with removable key and bottom of openable area to be between 800mm and 1100mm above floor level. 8000mm2 trickle vents required.

**RAINWATER GOODS**

Gutters to be molded upvc to match existing Rainwater pipe to connect to existing drains. All pipes to be fitted with rodding access to all changes of direction and at junctions. All new underground pipes to be 110mm UPVC laid 1:40 fall min. with granular encasement. Rainwater gully to be trapped.

**INTERNAL WALL CONSTRUCTION**

Non loadbearing internal walls shall be stud partitions comprising 75 x 75mm sole and head plates and 75 x 50 mm vertical studs at 600 mm maximum centres. 75 x 50mm noggins are to be incorporated between studs at 600 mm centres vertically.

50 x 38 mm intermediate noggins as required for radiators, shelves, socket and switch boxes etc. Stud Partitions to be dry-lined with 12.7 mm British Gypsum wallboard, Ames mechanical jointing, Topcoat finish.

80mm rockwool quilt in void and moisture resistant plasterboard and skim to bathroom walls

**VENTILATION**

Mechanical extractor capable of 15 litres / second to be vented through external Bathroom wall

Mechanical extractor capable of 60 litres / second (or 30 L/s adjacent to or incorporated in cooker hood) to be vented through external kitchen wall.

**ELECTRICS**

Electrics must be Part P compliant with full certification that all works are carried out in accordance with BS7671 to be provided, if not Part P credited then separate application to be made through Local Authority Building Control Dept.

**STAIRS**

Purpose made softwood stairs to BS 585:1989 with equal risings max 220mm and min 220mm going (42 degree pitch max.) handrail 900mm approx. above pitch line. Minimum headroom to be 2000mm.

Property of,  
**Adrian Dodds Joinery and Construction Ltd**  
Do not use without prior consent  
Tel - 07734 290708

-	-	-
Rev.	Revision Note	Date
Proposed alterations to 4 Hawthorn Terrace Shilbottle Northumberland - NE66 2XA		Scale 1:100
Title Proposed Elevations & Specification		Date 02.09.2021
		Sheet No. 002