

This copy has been made by or with the authority of Midlothian Council pursuant to Section 47 of the Designs and Patents Act 1988. Unless that Act provides a relevant exception to copyright, the copy must not be copied without the prior permission of the copyright owner.




- Seeding & Turfing**
- Amenity grass seeding, A22 Low maintenance seed mix @35g/m² by Germinal or approved equivalent
 - Bodpave porous paving grid system or approved equivalent seeded with amenity grass seeding as above, in 30:70 topsoil:sand mixture.
 - Wet Meadow Mix by Scotia Seeds or approved equivalent @ 3g/ m² as per manufacturers recommendations;
 - Wildflower/grass Seeding, Scotia Seeds Urban Pollinator Mix or approved equivalent @ 3g/ m²
 - Woodland underplanting seeding - Woodland Meadow mix by Scotia Seeds or approved equivalent @3g/m²
- Ornamental Shrub Planting**
- Ornamental Planting Mix 01 with shade tolerant species: Refer to planting schedules for species, percentages & quantities
 - Ornamental Planting Mix 02 structural ornamental species Refer to planting schedules for species, percentages & quantities
 - Ornamental Planting Mix 03 ground cover/ low level species Refer to planting schedules for species, percentages & quantities
- Proposed Tree Planting**
- EHS tree planting 1800x1800x600mm depth tree pit. Rootball secured with 3no anchors and mat & aeration pipe.
 - Multistem tree planting 1200x1200x500mm depth tree pit with 45° round timber post & aeration pipe.
 - Root barriers around tree pits as required to avoid clash with services/ drainage elements
- Proposed Woodland Planting**
- Periphery native woodland mix - higher proportion of understorey as planting plan (Trees shown are indicative only)
 - Core native woodland mix - higher proportion of transplants as planting plan (Trees shown are indicative only)
 - Periphery wet native woodland mix - higher proportion of understorey as planting plan (Trees shown are indicative only)
 - Core wet native woodland mix - higher proportion of transplants as planting plan (Trees shown are indicative only)
- Proposed Hedge Planting**
- Hornbeam hedge - 600mm wide, 1.2m height. 6no staggered plants per 1m with 1.2m high post & wire fence along centerline
 - Native mixed hedge - 1000mm wide, 1.2m height. 6no staggered plants per 1m with 1.2m high post & wire fence along centerline
- Hardworks**
- Gravel strip for car overhang at car parks & narrow strips between surfacing
 - Section of close boarded timber fence to prevent interference of car headlights with roundabout
- Existing Elements (to be retained/ protected)**
- Existing trees to be protected per tree constraints/ tree protection plan & tree survey to BS 5837:2012 Trees in relation to design, demolition and construction - Recommendations

Revision	Date	Description	Initials
P01	19.11.21	Issued for Approval	HL
P02	24.11.21	Minor changes due to updated overall layout around SuDS Basin	HL

IronsideFarrar
 Environmental Consultants
 111 McDonald Road, EDINBURGH, EH7 4NW
 0131 550 6500 | mail@ironsidefarrar.com
 EDINBURGH | BELLSHILL | MANCHESTER

Project No. 64000
 Project Name Sheriffhall South East Multi-let Development
 Client Buccleuch Property
 Title Landscape Proposals
 Planting Plan 1 of 2



Date 18.11.21 Paper Size A1 Quality Assurance ISO 9001:2015, 2025 UKAS Certificate GB02/54539
 Drawn By HL Checked by HL Copyright Acknowledgement Ordnance Survey © Crown Copyright 2019. All rights reserved. Licence No. AL100017968

Project	Origin	Location	Level	Type	Role	Class	Number
FOR APPROVAL					S4 - P02		
64000 - IFL - ZZ - XX - DR - L - 00 - 002							

Note: Please do not scale from this drawing