



CONSTRUCTION NOTES -

Garage doors and door frame replaced with cavity wall with timber/composite panel including insulation to replace but mimic garage door appearance to meet current thermal regs

Composite panels to be coloured

3 nr windows fitted to front infill with 1 fixed and 2 opening. All opening windows to be Escape windows, tilt and turn with clear openings greater than 0.33m² to meet regs. Sill height no greater than 1100mm from External FFL.

Windows to be upvc to match existing property windows

See other drawing for details and sizing of doors and windows

ELEVATIONS

Proposed change of use for Garage area
Springfield
Eardington
Bridgnorth

For Mr & Mrs Clarkson

Not to scale - see individual dimensions

Drawn - GC
Date - 20/01/22
Ref - Spring/GC/148/DOOR DETAILS