

ClassicBrick

COMPANY

TECHNICAL INFORMATION

Product Name: RURAL MULTI

Classic Brick Code: BRKRM(MET or IMP)

Production Type: THROUGH COLOURED
HANDMADE CLAY

Specification: BS EN 771-1

Size: 215 x 102.5 x 65mm
230 x 110 x 68mm*



Dimensional Tolerance:	T2
Range:	R1
Compressive Strength:	Mean 46N/mm ²
Water Absorption:	Mean 13%
Soluble Salts:	S2
Durability:	F2
Reaction to Fire:	Class A1
Bulk Density:	1530Kg/m ³
Pack Size	450No 360No*
Pack Weight:	1049Kg 995Kg*

Good practice from relevant British Standard relating to design & workmanship must be observed
Liability cannot be accepted for the performance of our product if the above is not adhered to.