

CHARGING POINT SPECIFICATIONS – From Ohme

- Domestic and commercial electric vehicle charger
- Automatically chooses the cheapest available electricity
- Provides up to 30 miles of range per hour
- Built in WIFI and app controlled
- Wall-mounted
- Includes Type 2 universal socket
- Sealed tethered unit - Car charge cable included (5m output/ 1m input)
- Single-phase
- Charging protocol: Mode 3 on IEC 62196 socket
- LED charging status indicator with LCD display
- Overcurrent protection: Requires 30mA RCBO Type A and 6mA DC installed at source
- Operating temperature: -25degC to +45degC
- Rated output: 7.2kW
- Amperage: 32A
- Rated voltage: 230V AC
- Frequency: 50 / 60 Hz
- Colour: Black
- IP rating: IP55
- Height: 239mm
- Width: 89mm
- Depth: 61mm
- Unit warranty: 3 year (installed by a accredited electrician)
- Cable warranty: 1 year
- Standards: EN 61851-1 and -2, BS7671:2018, CE
- Compatible vehicles: Nissan Leaf, Tesla Model X, Tesla Model 3, Jaguar i-Pace, VW e-Golf, BMW i3 and Kia Soul EV

