


DATASHEET



FLN10

230V IP65 10W LED FLOOD

www.mlaccessories.co.uk



MLA PART CODE	FLN10
DESCRIPTION	230V IP65 10W LED FLOOD
NET WEIGHT (KG)	0.189
FINISH	Black
DIFFUSER	Clear
DIMENSIONS (MM)	Height - 104 Width - 95 Depth - 28 Projection - 138 Overall Height - 160
CONSTRUCTION	Construction - Die-cast aluminium Construction 2 - & polycarbonate
CLASS	I
IP RATING	IP65
WATTAGE (W)	10
LAMP TECHNOLOGY	LED
LAMP INCLUDED	Yes
LUMENS (LM)	1085
LUMEN TOLERANCE	10%
EFFICACY (LM/W)	118.11
CIRCUIT WATTAGE (W)	9.21
CCT	4000K
LIGHT COLOUR	Cool White
CRI	>80
SDCM	<6
RUNNING CURRENT (A)	0.051
DISPLACEMENT FACTOR	>0.7
SVM	0.012
PST-LM	0.006
BEAM ANGLE (DEGREES)	100
LIFE SPAN (HRS)	30,000

L70B50 LIFESPAN (HRS)	30,000
DIMMABLE	No
OPERATING TEMPERATURE	-20~40°C
INPUT VOLTAGE	230V 50Hz
CABLE GLAND INCLUDED	Compression gland
WARRANTY	3year(s)
MANUFACTURED IN ACCORDANCE WITH	BS EN 60598
ORIGIN OF MANUFACTURE	China
DECLARATION OF CONFORMITY (HELD ON FILE)	Yes
EAN	5056270811117

Date Created: 11/03/2022 11:07

