

FULTON03: Mains sewer connection



FULTON04: Proposed toilet block



JB Equipment Ltd

Prefab Single Mains Toilet Block

Product Code: WC-SINGLE

£1,950.00 inc vat

£1,625.00 ex vat

Share: [f](#) [t](#) [p](#) [m](#)


In Stock | See ordering information tab

Quantity

1

Add to cart

Buy it now



Procedure for connection to an existing manhole. Entry will not be permitted into a manhole until a valid permit/SAAA is issued by Anglian Water. When a connection into an existing public sewer manhole is approved, specific guidance will be given. However, in general the following procedure will apply: The manhole should be core drilled and a short length of pipe inserted. All connections should be made soffit to soffit. The short pipes will be clayware or concrete, the use of porous concrete or plastic pipes is not acceptable. An appropriate channel bend (i.e. slipper) should be used to direct flow into the sewer. The channel bend must be of clayware. A rocker pipe shall be joined to the short pipe built into the manhole. The length of the rocker pipe shall be 600mm for a connection pipe not greater than 450mm in diameter.