




| Item | Qty | Description |
|------|-------|---|
| 1 | 6 No. | Lounge 1, Lounge 2, Dining Room, Main Bed 1, Main Bed 2, Bed 2 Box Sash Window (SI-I44-44) Timber : Grandis Hardwood (FSC Certified) Frame Profile: Historic/Flush Linings Sash Profile: Historic Lambs Tongue (18mm) CE/ WBG: No / No Sash Bar: Solid Sash Bar Finish: Traffic White - RAL 9016 Gasket: White Glazing: 6 No. 4mm Tough / 6 Kry / 4mm Tough-I.0 with a Bronze Historic Aluminium spacer Glazing Method: Putty, White Hardware: Polished Brass # Horns Additional Information 1 Type A 20mm Stops; Sash Eye 2 None Standard Lifts U _w Value: 1.8W/m2K Approx Weight: 104 kg |



| | | |
|---|--------|--|
| 2 | 18 No. | PSE + I Round Softwood (FSC) supplied in 2.5m lengths Colour: White - RAL 9016 Width (mm): 120mm Thickness(mm): 20mm I No. PSE Profile Setup |
|---|--------|--|



| | | |
|---|---------|---|
| 3 | 45.00 m | T1040 18x70mm Architrave Softwood (FSC) Supplied in 2.5m lengths Colour: White - RAL 9016 |
|---|---------|---|



| | | |
|---|--------|--|
| 4 | 7.50 m | T2025 25x145mm Windowboard MDF (FSC) Supplied in 2.5m lengths Colour: White - RAL 9016 |
|---|--------|--|

