



LANDSCAPING - WORKS SPECIFICATION

All plants and planting to conform with all the relevant latest British Standards

TREE PLANTING

Excavate pit 1.25 x 1.25 x 600mm deep, fork subsoil and sides of pit, spread roots evenly and backfill with good quality topsoil, firming 150mm layers
 Staking: Stakes to be 1.8m peeled pointed 'analised' softwood, minimum top diameter 20/30mm.
 Tie: One approved tie, attached within 250mm of top of stake.
 Mulch: 50mm depth of coarse grade pulvencised bark or equivalent, spread over planting pit.

TREE SPECIFICATION

MJD MALUS JOHN DOWNIE
 TT Tilia Tomentosa
 FM Field Maple
 CXM CRATAEGUS X MEDIA

ALL NEW TREE PLANTING TO BE
 (14-16cm girth @ 1m from ground level)

HEDGE SPECIFICATION

mixed native hedge where indicated (600 - 900 high bare rooted transplants
 350mm between plants in double staggered rows 500mm apart.
 Hedge to be 80% Hawthorn, 5% Hazel, 5% dog rose, 5% holly, 5% field maple

GENERAL

Water and drought: Ensure adequate suitable water is available for planting and subsequent maintenance.
 Maintenance: Maintain the planted areas until 12 months after the date for completion as follows:

- Hoe or otherwise remove weed.
- Make up levels where necessary with topsoil.
- Keep plants watered in hot weather early or later in the day.
- Spray against harmful insects or fungal attack.

Proposed Site Plan - (scale 1:200)



Proposed Site Visuals (n.t.s)



Proposed Site Visuals (n.t.s)

<p>Revision: A</p> <p>Material Finish Revised</p> <p>03/22</p>	<p>Date: 06/21</p>
<p>Client: Mr and Mrs Cope</p>	<p>Scale: 1:200</p>
<p>Project: Proposed Replacement Dwelling Crow Lane Farm Great Hale Lincolnshire</p>	<p>Original No: 212680-05A</p>
<p>Drawing Title: Proposed Site Plan and Visuals</p>	<p>Company: Rick Smith Design Architectural Design Consultancy 18 St. Michaels Skeddington, Lincolnshire, NG34 7DP Tel: 01529 414363 or 07786 838788 e-mail: rick@ricksmithdesign.com</p>