



Soft Landscape

- 1. Rose beds /Mixed beds around central fountain re-laid symmetrically (roses pruned to reduce ht) rest replanted.
- 2. Mixed Herbaceous Beds. Re-formed symmetrically and replanted.
- 3. Planting generally: replanted retaining specific structural shrubs.
- 4. Privet hedge - reduce height to 1m and interplant where gaps to rejuvenate. Reshape to regular formal hedge
- 5. Central horse chestnut Avenue, regularly pollarded.
- 6. Lawns. Returfed, with areas of lawn meadow, replant lost tree.
- 7. Tree removals: Refer to Plan TR1.
- 8. Moroccan Garden: New Planting to suit new layout, refer detailed plans.

Hard Landscape

- New 600 x 600 PC paving, with new crazy paving edging detail. Metal edge to demarcate between. (Suds drainage to Central Lawn).
- Restore, lift & relay PC slabs, to central area.
- Moroccan Garden - redesign- Porcelain paving pergola & raised beds, refer detailed dwgs.
- E1 - Japanese garden. Restored with new stone paving, bridge restored, bound gravel path, planting/gravel, 50%. TBC
- E2: English Garden. Lift and relay brick edging, new PC conc crazy paving, replant
- W1: Italian Garden: re-lay with stone angular crazy paving, dwarf hedge, statuary, replant.
- W2. Dutch Garden. Original brick + step paving - lift and re-lay/repoint, outer paving: new PC. Replant.
- E3 & W3: New patterned screen behind refurbished trellis to screen sustainable energy equipment.
- Refurbished urns supplemented with new to the same patterns.
- PC conc paving slabs to outer pavements & create dropped kerbs.
- New, compliant ramps to E4 & W4.
- All benches refurbished, new added

Drawing Title: **Proposed Illustrative Plan: Main Gardens**

Dwg No: **035_202**

SCALE: **NTS @A1**

Revisions
 Rev: A 23.6.21
 Rev: B 22.9.21
 Rev: C: 16.11.21 PLANNING

PROJECT: **Dolphin Square**
 CLIENT: **AXA IM**

