



Rural Multi Bricks From MBH PLC

TECHNICAL INFORMATION

Dimensional Tolerance:	T1
Dimensional Range:	R1
Durability against freeze/thaw:	F2
Active Soluble Salts Content Category:	S2
Gross Dry Density:	1460 kg/m ³
Compressive Strength:	Greater than 20 N/mm ²
Water Absorption:	Less than 15%
Thermal Conductivity:	0.45 W/m.K-50% 0.51 W/m.K-90%
Dimensions:	215mm x 102.5mm x 65mm

[Edit This](#)