

# BRE365 SOIL INFILTRATION RATE

**considine**  
civil + structural engineers

Project No: **4269** Sheet No. **1**  
Made By: **JEM** Revision: **P01**  
Date: **04/03/2021** Project: **18A SOMERSET ROAD**

## INFILTRATION TEST RESULTS PROVIDED BY CLIENT

Length (m):	1.50		
Width (m):	0.60	Depth at 75% Full (m):	0.38
Depth (m):	1.50	Time at 75% Full (mins.):	45.00
Void Ratio:	1.00		
		Depth at 25% Full (m):	1.13
		Time at 25% Full (mins.):	215.00
		$V_{p75-25}$ :	0.68
		$a_{p50}$ :	4.05
		$t_{p75-25}$ :	170.00
		$f$ :	1.63E-05 m/s

