



PIERS DETAIL

440 x 440 x 1950mm intermediate piers at approx. 5000mm centers. 1950mm piers to have pc caps, with DPC beneath.
Stone color to be same as house type.

SCREEN FENCING DETAIL

Alternate Vertical Slats 100x18mm & 50x18mm with 25mm Gaps. with 75x25mm splayed caping rail, Posts at 1800mm centres, All timbers to be redwood treated with 2No.coats stain.

AMENDMENTS:

Issue	Date	Description
A	Aug 2018	Title Box Updated.



Bellway Homes Limited
www.bellway.co.uk

SCOTLAND WEST
Bothwell House
Hamilton Business Park
Caird Street
Hamilton
ML3 0QA
Tel: 01698 477440

SCOTLAND EAST
6 Almondvale Business Park
Almondvale Way
Livingston
West Lothian
EH54 6GA
Tel: 01506 594420

Project:

STANDARD
EXTERNAL
DETAILS

Drawing:

PIER / FENCE DETAIL
STEEL POST

Scale: Date: Drawn:

1:20@A4 SEPT 16

Drawing No. Rev.

TF AA(9) 018

A