

CODE 5 LEAD FLASHING WITH MINIMUM
150MM UPSTAND

5MM CONTINUOUS STRIP
RIDGE VENT

MARLEY WESSEX ROOF TILES
(CLOSEST MATCH TO EXISTING)
COLOUR MATCH WITH EXISTING

NEW SVP TERMINAL

25MM CONTINUOUS STRIP
SOFFIT VENT

OBSCURED GLAZING

DOUBLE GLAZED DOOR TO
BS 6262 : PART 4 : 2005

PERPEND VENTS AT 1200 CRS MAX
AROUND PERIMETER AT HIGH AND
LOW LEVELS

FRONT ELEVATION AS PROPOSED

CONCRETE STEP
MAX RISE 170MM
MIN GOING 250MM

MARLEY MARVENT ROOF VENT
OVER MONOPITCH
20000MM² FREE AIR

UPVC PANNELLING REMOVED
ROUGHCASTED BLOCKWORK
BUILT OFF BRICKWORK

PAUL INNES
Construction Design Services

Tel 01236 432439
Mobile 07762 562628
email paul_innes@btinternet.com

I Hereby Certify That This Is A True And
Accurate Copy Of The Plans As Referred To
In The Application

Signed *Paul M Innes* Date *20/06/09*

Proposed Alterations To Dwellinghouse For:-
Ms M Devine
81 Muirhouse Road
Motherwell
ML1
Owner / Occupier

Drawn By	Paul M Innes
Date	Jun 2009
Scale	1:50
Drg. No.	290406/6