

relevant site conditions before any construction takes place.
DO NOT SCALE FROM THIS DRAWING.

STATUS - Planning



REAR ELEVATION

Alterations to existing window and opening:

- Existing uPVC window, lintol above and concrete cill below to be removed.
- Masonry outer leaf and timber frame structure to be removed below cill level.
- Existing masonry and timber framed reveals below cill level to be made good as required and new DPC and cavity stops fitted around window opening.
- New threshold cill installed to suit new door, with DPC below.
- Render finish to be made good below cill level as required.
- Mastic pointing around new door frames at head, jambs and cill on completion.



gd lodge architects

crown house 152 west regent street glasgow G2 2RQ
www.gdlodge.co.uk projects@gdlodge.co.uk
0141 332 6804

CLIENT
Mr. & Mrs. Black

PROJECT
Proposed Garden Room Extension
6 Foxglove Road, Newton Mearns

DRAWING
Rear (East) Elevation as Existing

SCALE	DATE	DRAWN BY	CHECKED BY
1:50	Feb.'21	CDA	
JOB NO.	DRAWING NO.	REVISION	
2847	PL-05		